

Which constitutive model do measured cavitation records prefer?

Spencer H. Bryngelson

August 13, 2026

Abstract

We compare seventeen constitutive models against laser-induced cavitation records in gelatin at three temperatures. The method is Bayesian model selection, with a noise scale measured from trial-to-trial spread and a prior that prices a model down where it merely reproduces a simpler one it contains.

A quadratic Zener solid – strain-stiffening elasticity *and* stress relaxation – wins at every temperature. It reaches $\chi^2/N = 1.23$ to 1.35 on the selection grid, and 0.96 refitted to its true optimum at 15°C . Neither ingredient suffices alone: at that temperature relaxation without stiffening reaches 1.98 , and both memoryless candidates land at 20 , where they fit each other to one part in a thousand. The stiffening term does no work at all without a relaxation mode to act on. Its advantage collapses as the gel warms, the clearest physical signal in the comparison.

We report the limitations plainly. The residuals are ceilings rather than estimates, because the winning model’s best-fitting region is partly unintegrable. More importantly, a good χ^2/N overstates how well the model does. The residual has lag-one autocorrelation 0.918 , so the 201 samples carry the information of about ten independent ones, and what remains is structure the model lacks rather than noise it failed to average away. The ranking survives this – a 3% change under a correlated likelihood – but the absolute claim does not.

We then ask what experiment would do better. Scored by parameter precision and by model discrimination, the criteria disagree, and both prove delicate: a criterion defined by an inner minimum is multimodal here, and every improvement to the optimizer lowers it.

Reformulating over design *measures* rather than single designs makes the problem convex, and the Kiefer–Wolfowitz equivalence theorem then certifies the answer. Over 480 candidates the optimum splits the runs three ways and beats the best single design by a D-efficiency factor of 5.74 – certified globally optimal at a gap of 9×10^{-10} , not merely the best found.

That formulation optimizes the wrong variable. Pricing the candidates – a trace of N samples costs N frames – puts the split between bubbles and frames inside the certified problem, and it is worth 0.9 to 10 nats against at most 1.3 for the geometry everything else optimizes. Two questions the design chapter left open close on the same terms: the screening threshold, which a maximin over the correlated-likelihood deflation removes, and the value of staging a budget, which is nil because one bubble at a geometry chosen for it settles every live operator rival. The temperature dependence closes nothing – with temperature held it is structurally unidentifiable, at any budget and any geometry.

Keywords: inertial microcavitation rheometry; model selection; Bayesian evidence; identifiability; optimal experimental design

1 Introduction

Inertial microcavitation rheometry infers the mechanical response of a soft material from the radius history of a single collapsing bubble [1]. A laser generates the bubble, high-speed imaging records $R(t)$, and a constitutive model is fitted to that trace. The strain rates reached, above 10^3 s^{-1} , are inaccessible to conventional rheometry, which is what makes the technique attractive.

The inference rests on choices that are rarely varied. A constitutive law is selected, a bubble-dynamics equation is assumed, thermal transport is included or neglected, and the resulting parameters are reported as material properties. Each choice conditions the answer, and the conditioning is seldom quantified.

We take the model comparison itself as the object of study. Candidate models are ranked by Bayesian evidence rather than by fit, since the candidates nest and best fit therefore selects the most flexible one [2]. We




Figure 1: Where this work sits in the measurement chain. A laser nucleates a bubble, imaging records how its radius changes, and a material model is fitted to that curve. The fitted stiffness and viscosity are then quoted as material properties. This paper concerns the two right-hand boxes: which model to believe, and which experiment to run so that the question can be answered. Ranking on goodness of fit alone does not work here, because a model with more parameters always fits at least as well as the simpler model inside it.

then ask what the records can settle, which turns out to be considerably less than the reported parameters suggest.

Three results follow. First, the likelihood depends on the product $g\alpha$ alone. The shear modulus is then set by where the prior box cuts a ridge, not by the data, and moving the box swings the model ranking by fifty nats.

Second, the bubble-dynamics operator – held fixed at Keller–Miksis in every published comparison we are aware of – is beaten on all three records by Gilmore/Tait. Third, the correlated residual that motivates richer constitutive models survives everything we tried against it: a second relaxation time, a rate-dependent one, fitting individual trials, and all six operators.

We also ask what experiment would settle the question. Treat the choice of model as one more unknown to be fitted, and one calculation says both how well an experiment separates the models and how well it pins the material. The answer comes with a proof of optimality – unusual for a design calculation, and following from a classical result [3].

Judged that way, the experiments analyzed here are near the best possible for the hardest of the three choices, and 24 to 41 times worse than the best for the two easiest.

2 Records and noise model

Each dataset is a set of repeated laser-induced cavitation events at one temperature, recorded as $R(t)/R_{\max}$. Figure 2 shows the mean trace and the trial-to-trial spread. We use that spread as the measurement noise. It is measured rather than assumed, so $\chi^2/N \approx 1$ means a model reproduces the record to within experimental repeatability.




Figure 2: Measured records. Line is the mean over trials, band is $\pm$ one standard deviation across trials at each time. The spread is the noise model.

Two samples are excluded before fitting. A trial reading above its own maximum radius is a tracking failure.




Figure 3: The Laplace expansion, and why the evidence is summed over modes. The integrand $e^{\ell}\pi$ is expanded about each maximum as a Gaussian, whose height and width give that mode’s contribution Z_k in closed form; the evidence is $\sum_k Z_k$, computed as a `logsumexp` over the distinct endpoints a multistart finds. Taking only the best mode discards the rest of the integral, which is the difference between an integral criterion and a minimum: a missed mode biases the total slightly, where a missed basin corrupts a minimum entirely. This is why `fit_candidate` returns every distinct endpoint rather than its winner.

And the $t = 0$ sample, where every trial agrees exactly, is a definition rather than a measurement: giving it an error bar would invent an uncertainty and let it constrain the fit.

Each candidate is evaluated on a log-spaced grid over its own parameters, at one resolution for every model, so grid luck cannot decide the winner. The evidence is a grid quadrature over that box. It carries three further pieces: the noise scale marginalized under a half-Cauchy prior, a redundancy factor down-weighting parameters where a model merely reproduces a simpler model it contains, and a BIC-style complexity penalty.

Trajectories are compressible [4]. The incompressible approximation changes the residuals by a factor of two to four and must not be used for these records.

3 Method

Four objects carry the analysis. Each is derived here rather than quoted, because the choices between them are not neutral and two of the errors this study corrected came from treating them as interchangeable.

3.1 The likelihood, and what it assumes

Each record gives a mean radius y_i at time t_i over 18 trials, with the trial-to-trial standard deviation s_i as the noise estimate. Modeling the observations as independent and Gaussian about the prediction $m_i(\theta)$,

$$p(y \mid \theta) = \prod_i \frac{1}{\sqrt{2\pi} \sigma_i} \exp \left[-\frac{(y_i - m_i(\theta))^2}{2\sigma_i^2} \right], \quad -2 \log p = \chi^2(\theta) + \sum_i \log(2\pi\sigma_i^2). \quad (1)$$

Three assumptions are buried here and each is separately checkable. *Gaussianity* is the weakest claim, and is reasonable because y_i is a mean over 18 trials. *Known* σ_i is not innocuous: using the sample spread as the true deviation understates uncertainty. Section 3.2 handles it by giving the noise scale a prior and integrating it out. *Independence* is the one that fails: the diagonal covariance in (1) says each residual carries fresh information, and Section 17.1 measures a lag-one autocorrelation of 0.90.

The deviations are not constant across the record. Optical tracking degrades where the wall moves fastest, so the variance is inflated by a logistic weight in the strain rate, $\sigma_i^2 = s_i^2/w_i$ with $w = w_0 + (1 - w_0) \logit^{-1}(\kappa(\dot{\epsilon}_{\text{th}} - |\dot{\epsilon}_i|)/\dot{\epsilon}_{\text{th}})$. This is a statement about the measurement, not the model, and it is why χ^2/N is dominated by the late record where the weights are large.

3.2 Integrating out the noise scale

Rather than trust s_i , introduce a single scale β multiplying every deviation, $\sigma_i \rightarrow \beta\sigma_i$. Substituting into (1),

$$\log p(y \mid \theta, \beta) = -\frac{\chi^2(\theta)}{2\beta^2} - N \log \beta + \text{const}, \quad (2)$$




Figure 4: Why this study ranks by evidence and not by fit. The constitutive candidates nest – NHKV is qKV at zero stiffening and qSLS at zero relaxation time – so a larger model can never fit worse, and the best-fitting candidate is simply the most flexible one. The evidence adds the Occam factor of Figure 25, which charges a model for prior volume the data does not use, and so turns a monotone quantity into one with an interior maximum. Everything downstream depends on that penalty being computed correctly, which is why the pathology in Figure 25 matters.

which depends on the data only through χ^2 and N . That is what makes the marginalization cheap: the forward model never re-enters, so

$$\log p(y | \theta) = \log \int_0^\infty p(y | \theta, \beta) \pi(\beta) d\beta \quad (3)$$

costs one pass over a quadrature grid rather than one solve per node. With the half-Cauchy prior $\pi(\beta) = (2/\pi)/(1 + \beta^2)$ the integral is done numerically on $\beta \in [0.05, 10]$.

Why marginalize rather than fit β ? Profiling at its best value gives $-\frac{1}{2}N [1 + \log(\chi^2/N)]$, and marginalizing is always smaller. The gap is an Occam penalty: a model that fits only by inflating its own error bars is charged for the inflation. Fitting β would hand that flexibility over for free.

3.3 Why the evidence, and not the best fit

From Bayes’ theorem, the posterior odds between two models are the prior odds times the ratio of

$$Z_M = p(y | M) = \int p(y | \theta, M) \pi(\theta | M) d\theta. \quad (4)$$

This is the only quantity that answers “which model should I believe” without an arbitrary complexity penalty. Comparing best fits cannot: a nested model never fits worse than the model containing it, so χ^2 ranks by flexibility.

Information criteria add a penalty $-2k$ for AIC, $k \log N$ for BIC. But BIC is an asymptotic approximation to $-2 \log Z$ assuming a regular, well-identified model with N large, and Section 3.5 shows this one is not identified in a direction. The integral itself assumes none of that.

The penalty appears explicitly on expanding (4) about the maximum. With $\hat{\theta}$ the best fit, $H = -\nabla^2 \log p(y | \theta)$ evaluated there, and $\theta = \hat{\theta} + \delta$,

$$Z_M \simeq p(y | \hat{\theta}) \pi(\hat{\theta}) \int \exp[-\frac{1}{2} \delta^T H \delta] d\delta = \underbrace{p(y | \hat{\theta})}_{\text{best fit}} \underbrace{\pi(\hat{\theta}) (2\pi)^{p/2} |H|^{-1/2}}_{\text{Occam factor}}. \quad (5)$$

The Gaussian integral is exact for a quadratic $-\log p$, so (5) is the Laplace approximation and its error is governed by the third derivative. Reading the second factor as $\pi(\hat{\theta}) \times (\text{posterior volume})$ makes its meaning plain: it is the fraction of the prior the posterior actually occupies, so a model needing fine tuning pays. This is the sense in which a good fit and a credible model differ, and it is what Freund and Ewoldt [2] argue should replace goodness-of-fit ranking in rheology.

One consequence matters later and is easy to miss. Because $|H|^{-1/2}$ grows as the posterior broadens, a sloppy direction *raises* the evidence. Model comparison therefore cannot detect non-identifiability – it rewards it – and the two questions must be asked separately.

3.4 The prior this study uses

Equation (4) needs $\pi(\theta | M)$, and a uniform box would make the answer depend on where the box was drawn. Two factors are used instead, both computed on the same grid the quadrature runs over.

The *bottleneck* maps each parameter to $u_j \in [0, 1]$ in logarithms, then takes the harmonic mean $H(\theta) = p / \sum_j u_j^{-1}$. Logarithms because the parameters span decades, where a linear map would encode the bounds rather than the physics.

The harmonic mean beats the arithmetic one here precisely because it is dominated by its smallest argument. A parameter driven to the bottom of its range drags the whole prior down. The reasoning: a parameter the data pushed to a boundary is one the model did not need.

The *redundancy* weight asks whether a model merely emulates a simpler one it contains. For a candidate and each nested child, the relative stress mismatch F is mapped by $F^n / (F^n + \tau^n)$ against the resolvable scale τ . That gives a number near 0 when the parent imitates the child, approaching 1 when it does something genuinely different.

The weight is the *minimum* over children. A model that can imitate any one simpler model is redundant there, however different it looks from the rest.

3.5 The Fisher information, and what its eigenvectors are

Differentiate $-\log p$ twice at fixed data and take the expectation over noise. The term containing $\partial^2 m$ vanishes because $\mathbb{E}[y_i - m_i] = 0$, leaving

$$F_{jk} = \sum_i \frac{1}{\sigma_i^2} \frac{\partial m_i}{\partial \theta_j} \frac{\partial m_i}{\partial \theta_k} = (J^\top J)_{jk}, \quad J_{ij} = \frac{1}{\sigma_i} \frac{\partial m_i}{\partial \theta_j}, \quad (6)$$

so the Fisher information is exactly the Gram matrix of the whitened sensitivities – no approximation, given (1). Near the optimum $\Delta \chi^2 \simeq \Delta \theta^\top F \Delta \theta$, so the surface of constant misfit is the ellipsoid $\Delta \theta^\top F \Delta \theta = c$. Diagonalizing $F = V \Lambda V^\top$, its axes are the eigenvectors and their half-lengths are $\sqrt{c/\lambda_k}$: a small eigenvalue is a long axis, a direction along which the data barely object.

The Cramér–Rao bound gives this statistical force. For any unbiased estimator, $\text{Cov}(\hat{\theta}) \succeq F^{-1}$, so F^{-1} is the best achievable covariance and its eigen-decomposition is the confidence ellipsoid. The standard deviation along direction k is $\lambda_k^{-1/2}$, and the ratio $\kappa = \lambda_{\max}/\lambda_{\min}$ measures how far the problem is from determining all directions equally.

Two conventions are load-bearing. Taking $\theta = \log(\text{parameters})$ makes an eigenvector a power law: moving along v sends $\Delta \log g = v_g t$ and $\Delta \log \alpha = v_\alpha t$, so $g \propto \alpha^{v_g/v_\alpha}$ and the exponent is read directly off the components. Second, sensitivities taken with respect to a scaled coordinate $u_j = (\log \theta_j - a_j)/w_j$ give $\Delta \log \theta_j = w_j \tilde{v}_j$, so the exponent is $(w_g \tilde{v}_g)/(w_\alpha \tilde{v}_\alpha)$. With box widths of three and four decades that is a 25% correction. Getting it wrong produced a spurious agreement earlier in this work.

Finally, F is the observability Gramian of the system augmented with $\dot{\theta} = 0$: identifiability and observability are the same statement. The distinction that matters is *structural* unidentifiability, where F is singular and no data can help, against *practical* sloppiness, where F is invertible but ill-conditioned. Here $\lambda_{\min} = 5.2 \times 10^{-2} \neq 0$ and the profile likelihood has a genuine minimum, so the problem is the second – which is why a different experiment can fix it.

3.6 What correlated residuals cost

Equation (1) counts N independent pieces of information. If instead the residuals have autocorrelation ρ_k at lag k , then for a sum of N correlated terms $\text{Var}(\sum r_i) = N\sigma^2(1 + 2\sum_{k \geq 1} (1 - k/N)\rho_k)$, so the information is that of

$$N_{\text{eff}} = \frac{N}{1 + 2\sum_{k \geq 1} \rho_k} \quad (7)$$

independent samples, and parameter uncertainties are understated by $\sqrt{N/N_{\text{eff}}}$. The sum is truncated at the first negative ρ_k – Geyer’s initial positive sequence – because the long tail is estimated from few pairs each and contributes sampling error rather than signal.




Figure 5: What lag-one autocorrelation measures, and what it does not. Sampled at the $N = 201$ points of these records, lag-one is close to a measure of how much of a residual is *smooth*: white noise gives 0.04, a single smooth excursion 1.00, a mixture that is three-quarters smooth 0.92. It does not say what made the residual smooth – model discrepancy, variation between bubbles and a slow calibration drift are alike in this statistic. The qSLS residual gives 0.918; the trial deviations from the mean, with no model fitted at all, give 0.859. Most of the smoothness the fit residual shows is therefore already in the data.

The correct remedy is a covariance with off-diagonal terms, not a larger σ . Taking $C_{ij} = \sigma_i \sigma_j \exp(-|t_i - t_j|/\tau)$, the Cholesky factor $C = LL^T$ gives the generalized least squares form

$$-2 \log p = r^T C^{-1} r + \log |C| + \text{const} = \|L^{-1} r\|^2 + 2 \sum_k \log L_{kk} + \text{const}, \quad (8)$$

which is what **FieldObservation** computes. Inflating σ instead would treat structure as noise: it widens the error bars while leaving the parameter estimates biased, which is the failure Brynjarsdóttir and O’Hagan warn about.

3.7 Which design criterion, and why they disagree

An experiment is chosen by a scalar summary of F . The classical family is

$$\text{D: } \max \det F, \quad \text{A: } \min \text{tr } F^{-1}, \quad \text{E: } \max \lambda_{\min}, \quad \text{c: } \min c^T F^{-1} c. \quad (9)$$

D minimizes the volume of the confidence ellipsoid, A its mean squared axis length, E its longest axis, and c the variance of one nominated combination. They rank designs differently because they summarize the same spectrum differently. The choice states what one wants to learn.

For identifiability the relevant fact is a scaling argument. A design change that only amplifies signal – more samples, less noise, a larger bubble – sends $F \rightarrow sF$. Then $\det F \rightarrow s^p \det F$ and $\lambda_{\min} \rightarrow s \lambda_{\min}$, so D and E both improve, while

$$\kappa = \frac{\lambda_{\max}}{\lambda_{\min}} \quad \text{is unchanged.} \quad (10)$$

Degeneracy is a property of the *eigenvectors*, not the eigenvalues. Only a design that rotates them can remove it. That is why the E-optimal search preferred a larger bubble while conditioning preferred a gentler collapse: more signal against better separation.

The c-optimal choice carries a small trap. Nominating c as the sloppy direction *of the present design* optimizes for a direction that moves once the design changes. In this study that criterion recommended the opposite of the right answer.

When the model itself is in doubt, none of these apply: all presuppose the model whose F is being computed. T-optimality asks instead for the design maximizing the discrepancy between rival predictions, $\max_{\xi} \|m_1(\hat{\theta}_1; \xi) - m_2(\hat{\theta}_2; \xi)\|$, and privileges neither.

4 Identifiability of the constitutive parameters

The winner fits, but not every parameter it contains is measured by these data.

Why the trade exists

Write $\hat{g} = G/p_\infty = 1/\text{Ca}$ for the nondimensional modulus and $\lambda = R_{\text{eq}}/R$ for the stretch the stress law sees. The equilibrium stress the Maxwell arm relaxes toward is

$$Z_e = R^3 \left[\frac{3\alpha-1}{2} \hat{g} P(\lambda) + 2\alpha \hat{g} Q(\lambda) \right], \quad \begin{aligned} P(\lambda) &= 5 - \lambda^4 - 4\lambda, \\ Q(\lambda) &= \frac{27}{40} + \frac{1}{8}\lambda^8 + \frac{1}{5}\lambda^5 + \lambda^2 - \frac{2}{\lambda}. \end{aligned} \quad (11)$$

Collecting powers of α separates it into two terms with different parameter dependence,

$$Z_e = \hat{g} \alpha A(\lambda) + \hat{g} B(\lambda), \quad A = R^3 \left[\frac{3}{2} P + 2Q \right], \quad B = -\frac{1}{2} R^3 P. \quad (12)$$

This is exact; it reproduces the implemented expression to 2.5×10^{-14} over random states. Only the first term carries α , so $\hat{g}\alpha$ and $\hat{g}$ are separately determined only while *both* terms contribute.

They do not, at depth. As λ grows, $Q \rightarrow \frac{1}{8}\lambda^8$ dominates every other term in either bracket, so $A \rightarrow \frac{1}{4}R^3\lambda^8$ while $B \sim \frac{1}{2}R^3\lambda^4$, and

$$Z_e \rightarrow \frac{1}{4} \hat{g} \alpha R^3 \lambda^8, \quad (13)$$

a function of the *product* $\hat{g}\alpha$ alone. The likelihood cannot then distinguish a soft material that stiffens sharply from a stiff one that barely stiffens. Holding Z_e fixed in (12) gives the trade in closed form,

$$\frac{\partial \log \hat{g}}{\partial \log \alpha} = -\frac{\alpha A}{\alpha A + B} \rightarrow -1 \quad (\lambda \rightarrow \infty), \quad (14)$$

and the share of the signal that separates the two parameters is

$$\frac{|\hat{g}B|}{|\hat{g}\alpha A|} = \frac{|B|}{\alpha|A|} \simeq \frac{2}{\alpha\lambda^4}. \quad (15)$$

Equations (14) and (15) are what the measurements see. These records collapse to $\lambda = 2.215$, where (14) gives -0.981 against -0.99 from the Fisher curvature – a prediction from the constitutive law, not a fit. The profile likelihood returns -0.80 because it averages over a range of λ , and the exponent is -0.861 at $\lambda = 1.5$. Separability falls as λ^{-4} : it is 2% of the signal at $\lambda = 2.2$ and 16% at $\lambda = 1.5$.




Figure 6: The two terms of (12) against collapse depth. Left: αA , which depends on the product $g\alpha$, outruns B , which carries g alone. Right: their ratio, the share of the signal that can separate the two parameters, following $2/(\alpha\lambda^4)$ once the collapse is deep. It is 2% at the depth these records reach and 16% at $\lambda = 1.5$.

What the Fisher information measures

For Gaussian observations with known deviations the log-likelihood is $-\frac{1}{2} \sum_i (y_i - m_i(\theta))^2 / \sigma_i^2$ up to a constant, so with the whitened sensitivity $J_{ij} = \sigma_i^{-1} \partial m_i / \partial \theta_j$ the Fisher information is exactly $F = J^\top J$, and $\Delta \chi^2 \simeq \Delta \theta^\top F \Delta \theta$. Taking θ to be the logarithms of the parameters makes the eigenvectors read as power-law combinations: along an eigenvector v the ratio v_g/v_α is the exponent in $g \propto \alpha^{v_g/v_\alpha}$. This is also the observability Gramian of the system augmented with $\dot{\theta} = 0$, which is why identifiability and observability are the same statement here.

One caution, since it caught us. Sensitivities taken with respect to a unit cube $u_j = (\log \theta_j - a_j)/w_j$, rather than $\log \theta_j$ directly, give eigenvector components that carry the box widths. Then $\Delta \log \theta_j = w_j \tilde{v}_j$, so the exponent is $(w_g \tilde{v}_g)/(w_\alpha \tilde{v}_\alpha)$, not $\tilde{v}_g/\tilde{v}_\alpha$. With w of three and four decades the two differ by 25%.




Figure 7: What an eigenvector means, shown rather than defined. The parameters are moved the same distance in log-space along each eigenvector. Along the sloppy direction a 27% change in the modulus, compensated by 38% in the stiffening, leaves the trajectory inside the measurement noise; along the stiff direction a change of the same size is obvious. The data cannot see the first and cannot miss the second.

Modulus and stiffening trade against each other. Two independent analyses agree. The Fisher information at the fitted optimum has an eigenvalue spectrum spanning six decades. The eigenvector of its smallest eigenvalue is almost purely a shear-modulus-against-stiffening direction: weights -0.796 and $+0.604$, against contributions of -0.003 and -0.032 from viscosity and relaxation time. Separately, profiling the likelihood in α – fixing it and re-optimizing everything else – gives $g \propto \alpha^{-0.80}$ across two decades. Sampling the posterior gives a third, independent measurement: its widest direction is $(-0.682, +0.002, -0.082, +0.727)$ in the logarithms of $(g, \mu, \lambda_1, \alpha)$, and $\log g$ is 98.7% anticorrelated with $\log \alpha$.

The three exponents are -0.99 from local curvature, -0.94 from the posterior covariance, and -0.80 from the profile. They agree the trade is near-reciprocal and disagree in the third digit. That is expected rather than troubling: the valley is curved, so a curvature estimate at one point and a chord across two decades measure different slopes. The correlation is the more robust statement.

So viscosity and relaxation time are cleanly determined, while modulus and stiffening are constrained only in combination. The identifiable quantity is closer to $g \alpha^{0.8}$ than to either alone, and a fitted α should be reported with its correlation to g rather than as an independent material property.

Figure 9 shows why the four estimates in this study disagree about g by an order of magnitude while agreeing about the fit. They are different points on the floor of one flat-bottomed trench.




Figure 8: Left: the 95% region from the inverse Fisher information, 10.7 long and 0.015 wide in log-parameters – an axis ratio of 706, which is why it draws as a line, and the analytic slope of -0.981 lies along it. Right: the misfit measured by re-solving at perturbed parameters, not the quadratic approximation. Moving along the stiff direction costs 10^4 in $\Delta\chi^2$; moving the same distance along the sloppy one stays below the 95% threshold, so the parameters may shift by a factor of $e \approx 2.7$ without the data objecting.




Figure 9: χ^2/N over the modulus-stiffening plane, at the fitted viscosity and relaxation time. The dashed line is $g \propto \alpha^{-0.80}$, predicted from the Fisher curvature at a single point; it lies along the floor of the valley. Four “best fits” from four methods are strung out along that floor rather than disagreeing with one another. The white region at upper right is where the model is not physical.

The stiffening is nonetheless identified, once the prior allows it. Sampling with the ceiling on α placed at 1, 10 and 100:

ceiling	log evidence	median α	97.5%
1	2162.9	0.85	0.97
10	2173.9	6.37	9.04
100	2172.4	5.27	8.73

Widening the prior tenfold moves the median only from 6.37 to 5.27, and the evidence by 1.5 out of 2173. So α is identified near 5, with 97.5% of posterior mass below about 9. A prior-dominated parameter would have tracked its bound. The ceiling of 1 shows what genuine truncation looks like: the median pins against it and 11 log units of evidence are lost.

This corrects a natural reading of the profile likelihood alone, which appears flat to the boundary only because the boundary sits where the posterior’s upper tail does.




Figure 10: Left: the Fisher spectrum at the optimum, six decades between the stiffest and sloppiest directions, with the sloppiest being modulus against stiffening. Right: the posterior for α against the ceiling imposed on its prior. It tracks the ceiling while truncated and departs from it once the ceiling is loose, which is what distinguishes an identified parameter from a prior-driven one.

5 Results

Table 1 and Figure 11 give the outcome. The quadratic Zener model qSLS – strain-stiffening elasticity with stress relaxation – wins at every temperature. The ordering beneath it separates into three tiers: models with both ingredients, models with relaxation only, and memoryless models.

Figure 12 overlays the winning model on the data it was selected against.

5.1 Reading the posteriors

The model posteriors saturate. The winner takes essentially all the mass and the runners-up are reported as 10^{-29} or smaller. Do not read these magnitudes literally.

Evidence differences scale with sample count. With roughly 3600 samples, a modest per-sample difference in fit compounds into an astronomical Bayes factor. The defensible reading is ordinal: the winner is decisive

Table 1: Best χ^2/N on the selection grid by model class – the best node, not the best fit; Section 5.2 refits and reaches 0.962 for qSLS at 15 °C. Values near 1 indicate a fit within experimental repeatability.

	15 °C	23 °C	33 °C
qSLS (stiffening + relaxation)	1.35	1.33	1.23
SLS (relaxation, linear elasticity)	2.94	1.85	1.41
viscoelastic fluids	5.3–5.7	4.5–4.7	1.9–2.1
memoryless	12.6–16.7	–	–




Figure 11: Best χ^2/N on the selection grid for every candidate, all three temperatures, logarithmic scale. The dashed line is the measurement-noise floor.




Figure 12: The selected model against the measured band it was fitted to.

and the ordering means something, the magnitudes do not. Quote the residual χ^2/N . Section A.6 sets out which normalisation each reported log evidence uses, and why numbers from different sections must not be differenced.

5.2 How good are the fits, really?

The table above reports the best χ^2/N found on the evaluation grid. Two questions follow, with different answers. How well does the winning model fit? And how much does a good χ^2/N entitle us to claim?

The grid understates the fit. The model-selection grid evaluates each candidate at log-spaced parameter nodes, so its best value is the best *node*, not the best fit. Refitting each model to the 15 °C record by multistart Gauss–Newton with analytic Jacobians – eight starts from a Latin hypercube over the wide prior box, taking the lowest – gives:

model	parameters	χ^2/N	lag-one ρ	N_{eff}	χ^2/N_{eff}	inflation
qSLS	4	0.962	0.918	10.3	18.9	4.43
SLS	3	1.984	0.932	7.1	56.6	5.34
qKV	3	20.18	0.948	13.4	302	3.87
NHKV	2	20.16	0.948	13.4	302	3.87

At its true optimum qSLS reaches $\chi^2/N = 0.96$ rather than the grid’s 1.35, which confirms in a second way that the tabulated residuals are ceilings. The ordering is unchanged, and the gaps are large: relaxation without stiffening doubles the residual, and both memoryless models sit twenty times above it.

Stiffening buys nothing without relaxation. qKV and NHKV differ only by the stiffening exponent α , and they fit identically: 20.18 against 20.16, one part in a thousand on a residual twenty times too large. The strain-stiffening term is decisive alongside a relaxation mode and worth nothing without one.

That is sharper than the evidence ranking alone. It is not that qKV is a worse model than qSLS; its extra parameter does no work at all. It also explains why the temperature trend is carried by the interaction of the two mechanisms rather than by either alone.

But $\chi^2/N \approx 1$ does not mean the fit is within noise. The statistic χ^2/N compares the residual to its expectation under the assumption that the N residuals are independent draws of known scale. They are not. The lag-one autocorrelation of the qSLS residual is 0.918, and by the Geyer initial-positive-sequence estimator [5] of (7) the 201 samples carry the information of about $N_{\text{eff}} = 10$ independent ones. Dividing by that count instead gives 18.9.

That number is not a calibrated test. For correlated residuals the correct statistic is $r^\top \Sigma^{-1} r$ with the true covariance, not χ^2 rescaled by an effective count. But its message is robust, and it is the opposite of the headline’s.

A residual with $\rho = 0.918$ is not noise the model failed to average away. It is *structure* the model does not contain. The fit is excellent in that no candidate does better, and not excellent in that it is inconsistent with the measurement error.

The classical test agrees, and says more. The argument above rests on lag-one autocorrelation, which Section 17.1 shows is a blunt instrument. There is a standard test for the same question and these records already carry what it needs: replicates. The trial spread at each time is *pure error*, costing no model, so the residual of the mean splits into that and what the model cannot follow,

$$F = \frac{J \sum_i (\bar{y}_i - \hat{y}_i)^2 / (k - p)}{(J - 1) \sum_i s_i^2 / k(J - 1)}, \quad (16)$$

with J trials at k times and $p = 4$ parameters. The records do not carry equal replication: J is 18, 14 and 7.

record	J	χ^2/N	pure error	lack of fit	F	corrected
15 °C	18	0.973	5.20×10^{-4}	7.36×10^{-3}	14.2	23.3
23 °C	14	1.017	1.86×10^{-3}	5.47×10^{-3}	2.9	4.8
33 °C	7	1.130	1.91×10^{-3}	6.23×10^{-3}	3.3	5.4

Degrees of freedom are 197 against 3417 at 15 °C and fall with J elsewhere, so the five percent critical value is near 1.2 throughout. Every record shows lack of fit. The conclusion is the one above, reached with none of the same machinery.

Two things make it worth the page. It gets the factor of J right by construction — the fit compares the *mean* of the trials against the spread *between* them, and the J in the numerator is that missing $\sqrt{J}$ — and it is conservative in a direction we can quantify: 39.3 % of the trial variance is bubble-to-bubble parameter spread rather than measurement, so pure error is inflated and the corrected column divides that share out.

It also separates the records, which lag-one does not: those values are 0.919, 0.968 and 0.911, effectively identical. Two things drive the separation and both are real. 15 °C repeats itself about three times more tightly, and it was run with more than twice the replicates of 33 °C — replication is what buys power to detect lack of fit, so the F column correctly rewards it. Removing the replicate factor, the systematic misfit variance stands at 0.79, 0.21 and 0.47 of pure error, so the ordering survives but the spread is milder than 14.2 against 3.3 suggests.

The strongest evidence that the model is incomplete therefore comes from the record with the best apparatus and the most repeats, not from the worst fit.

The p -value is not usable: F assumes independent errors across time and these are correlated at 0.918. The ratio needs no such assumption, and is read here as an effect size.

Three things follow, and they should be read together.

1. *The ranking survives.* Refitting under a correlated likelihood with a Cholesky whitening of an estimated AR(1) covariance changes the qSLS–SLS evidence gap by 3%. What the correlation destroys is the absolute claim, not the comparison, and the comparison is what the study is for.
2. *The denominator is the wrong yardstick.* The scale σ_i is the trial-to-trial spread. Much of that is variation in the parameters between bubbles, not error in measuring any one of them. A χ^2 formed against it is not comparing the model to measurement precision at all.
3. *The misfit is in the early record*, not where the tracking is hardest. Restricting the fit to a later window makes χ^2/N worse, 0.97 to 1.95, and does not whiten the residual. The structure cannot be excised by discarding the awkward part of the record.

The honest summary: qSLS is the best available description of these records by a wide margin, it is measurably incomplete, and the size of what is missing is better read from the residual’s correlation than from its magnitude. What that incompleteness costs the parameters is a separate question from whether it exists, and Section 10 answers it: on these records the model-form budget is larger than the posterior width by one to two orders of magnitude.

5.3 What the trial spread actually is

The likelihood of Section 3.2 treats the residuals as independent draws whose scale is the trial-to-trial spread s_i . Two assumptions are buried in that, and both are wrong in ways that matter for how the numbers above should be read.

Part of the spread is the parameters, not the measurement. If the 18 trials differed only by measurement error, their deviations from the trial mean would be white and point nowhere in particular. They do neither.

The singular spectrum of the 18×201 deviation matrix puts 53.9% of the variance in one component, where white noise would give 5.9%. Projecting each deviation onto the span of $G = \partial(R/R_{\max})/\partial\theta$ for the six parameters $(R_0, R_{\text{eq}}, g, \mu, \lambda_1, \alpha)$ captures 39.3% of the variance against a chance level of $6/201 = 3.0\%$. Noise does not align with a six-dimensional subspace of a 201-dimensional space by accident.

The natural physical reading is that each bubble has its own parameters, drawn from a population: $\theta_j \sim \mathcal{N}(\theta_{\text{pop}}, \Sigma)$. The mean trace then has covariance

$$C = \frac{1}{J} (G \Sigma G^\top + \sigma_{\text{meas}}^2 I), \quad (17)$$

low rank plus diagonal rather than diagonal.

But the dominant mode is not parameter variation, and a refit proves it. The projection above is a statement about a *linearization*: it asks whether the deviations lie in the span of G evaluated at one point. That test cannot exclude variation large enough to turn the Jacobian between trials, and it is the only test this argument had. So each trial was fitted on its own — 39 fits across the three records, in the identified coordinates of Section 10.

Giving every trial its own parameters does not absorb the leading mode. It keeps its shape and takes a *larger* share of the reduced residual:

record	mode 1 before	mode 1 after	$ \cos $ between them
15 °C	0.539	0.412	0.699
23 °C	0.681	0.772	0.987
33 °C	0.720	0.835	0.943

An absorbed mode collapses; these do not. Only 15 °C shows partial absorption.

Those three axes are the MATERIAL ones, though, and the equilibrium radius was held at $R_{\text{max}}/\text{stretch}$ — one value for every trial in a record — so that refit could not have absorbed variation in the initial condition however large it was. That is not a pedantic gap. The mode is 97 to 98% post-collapse, and the afterbounce period is set by the gas the bubble is left with, so R_{eq} is both the quantity nucleation is least repeatable in and the one whose variation appears after the first collapse rather than during it.

Refitting with R_{eq} free over the $\pm 11\%$ its prior allows:

record	raw	material only	$+ R_{\text{eq}}$	$ \cos $ to raw
15 °C	0.539	0.412	0.338	0.683
23 °C	0.681	0.772	0.791	0.988
33 °C	0.720	0.835	0.717	0.955

At 33 °C the answer is clean: no fit rests on a bound, R_{eq} moves by 3.0% between trials, and the mode keeps its shape at $|\cos| = 0.955$. Freeing the initial condition does not absorb it.

At the other two records the test is *inconclusive rather than negative*, and the reason is worth stating instead of burying. Seven of eighteen fits at 15 °C and four of fourteen at 23 °C rest against the upper bound of 1.111: those trials wanted a larger equilibrium radius than the prior permits, and were cut off. The pinning is also one- sided, which reads as a systematic offset in the record’s stretch rather than as scatter between bubbles — a calibration question, and a different one from this section’s.

Nor is it how the bubble starts moving, which was the last axis available. Every test above varies what the bubble *is*. None varies how it *starts*, and that gap mattered: the mode is 97 to 98% post-collapse, what a bubble carries into its rebound is set by the energy it goes in with, and every fit here begins at R_{max} with zero wall velocity — asserting that the imaged maximum is a turning point of a free collapse.

Refitting each trial with an initial wall velocity free *and* the stretch free, over boxes wide enough that nothing pins:

record	raw	material	$+ R_{\text{eq}}$	$+ R_{\text{eq}} + u_0$	$ \cos $ to raw
15 °C	0.539	0.412	0.338	0.340	0.678
23 °C	0.681	0.772	0.791	0.800	0.987
33 °C	0.720	0.835	0.717	0.840	0.945

Nothing moves. The leading share is unchanged to within a percent on every record, and the mode keeps its shape at $|\cos| = 0.987$ and 0.945 . Nothing pinned, so the boxes were not the constraint.

There is real scatter in both quantities — u_0 spreads by 0.008 to 0.016 of the Rayleigh velocity across trials, over ranges from -0.047 to $+0.009$, and R_{eq} by 2.0 to 6.4%. It simply is not what carries the mode.

So the claim can be made at full strength rather than narrowly. *Whatever carries half to three-quarters of the trial scatter is not any quantity this model has*: not the material parameters at each trial’s own optimum, not the equilibrium radius over a box that does not cut off, and not the initial wall velocity. Four absorptions attempted, four failed, and the last two were the configuration quantities that the mode’s position after the collapse pointed at most directly.

It is largely the clock, and the acquisition data says so directly. Each of those tests varied a property of the bubble. The one quantity that could not be tested was the one every trace is divided by before it arrives: its own R_{max} . The acquisition record carries it — 835 events, each with a measured R_{max} , a measured R_{eq} and an un-normalised trace — and two facts follow immediately.

The scatter is in the scale, not in the ratio. Per event, R_{max} has a coefficient of variation of 0.25, 0.28 and 0.23 in bins around 15, 23 and 33 °C, while the stretch $R_{\text{max}}/R_{\text{eq}}$ has 0.052, 0.066 and 0.062 about a mean near 8.1 at every temperature. The absolute scale varies four times more than the ratio this document has been treating as the uncertain one.

And a scatter in R_{max} is a scatter in the clock. $R(t)/R_{\text{max}}$ is a near-universal function of t/t_c with $t_c \propto R_{\text{max}}$, so bubbles differing only in size trace one curve at different rates, and the deviation that produces is $\partial R/\partial \log t_c = -t\dot{R}$ — small early, growing as phase error accumulates, and therefore concentrated after the collapse. Which is where this mode has been all along.

On the raw traces the identification is not marginal:

	events	leading share	$ \cos $ to $-t\dot{R}$	chance
raw, 12 °C to 18 °C	253	0.882	0.951	0.075
raw, 20 °C to 26 °C	100	0.869	0.976	0.075
raw, 30 °C to 36 °C	84	0.861	0.973	0.075
processed, 15 °C	18	0.539	0.572	0.071
processed, 23 °C	14	0.681	0.581	0.072
processed, 33 °C	7	0.720	0.518	0.071

In the acquisition data the dominant mode *is* the time dilation, at $|\cos|$ of 0.95 to 0.98 against a chance level of 0.075, carrying seven-eighths of the variance. There is nothing to explain there.

What reaches this document is the residue. The processing already removes most of it: the timescale scatter the records imply is 1.0 to 2.1 percent against the 22 to 28 measured per event, a factor of 15. What survives still aligns with the dilation at 0.52 to 0.58 and carries 24 to 27 percent of the trial variance — *the largest single share anyone has attributed to this mode*, against 0.467 for the best of nine linearised parameter directions.

It is not the whole of it. Projecting the dilation out leaves a leading mode overlapping the original at $|\cos|$ of 0.81 to 0.85, so a fifth to a quarter is accounted for and the rest is not. But the character of the question has changed: this is no longer a mode with no candidate, it is a mode with one identified mechanism carrying a quarter of it and a remainder that the same normalisation may well be leaving behind in a form the linear direction does not capture.

Two further facts locate it without naming it. It lives in the *rebound*: 98.0% and 97.2% of its squared length falls after the collapse window at 23 and 33 °C, while the identifiable discrepancy of Section 10 sits 65 to 69% in the *first collapse*. And it is not one curve: on a common t/t_c grid the three records’ leading modes overlap at $|\cos|$ of 0.075, 0.252 and 0.082, against 0.050 for unrelated curves of that length. A shared curve would have been the apparatus, which no constitutive law could absorb. This is not shared either.

What the refit does give is Σ . Regressing deviations onto G inherits the g - α degeneracy of Section 3.5 and returns $\text{sd}(\log g) = 159$, which is why this document previously reported Σ as not estimable. The per-trial fits estimate it directly, in the identified coordinates where no such degeneracy exists:

record	μ	$g\alpha$	λ_1
15 °C	14.7%	22.8%	60.2%
23 °C	33.9%	20.2%	58.9%
33 °C	19.2%	20.3%	117.1%

as coefficients of variation in log coordinates. These are overestimates — a single trial’s measurement noise is not separable from the trial spread with this data, so each fit is weighted by a scale that already contains what is being estimated. They are nonetheless the first direct measurement of Σ here, and Section 15 is what they buy.

One entry has to be read with Section 8. Fitting R_{eq} per trial over a box wide enough that nothing is cut off gives spreads of 1.9, 6.7 and 3.1 percent about medians of 1.099, 1.063 and 1.032 — so most of what a narrow box would have called scatter in the initial condition is a common offset in the stored stretch, and only the remainder belongs in Σ .

It is not what makes the residuals correlated. The natural hypothesis is that the lag-one correlation of the fit residual is this same effect. Whitening by (17) tests it directly:

covariance	χ^2/N	lag-one ρ
diagonal (independent)	17.54	0.758
hierarchical, (17)	21.96	0.516

The correlation falls by about a third, and most of it survives. χ^2 gets *worse*, so the residual sits in directions where C is small. The dominant term is model-form error, not variation between bubbles. Both effects are real and the model-error one is larger, which separates two things Section 17.1 had conflated.




Figure 13: What the trial spread is, and what it does not explain. Left: the singular spectrum of the eighteen trial deviations. Independent measurement error would put an equal share in every component (dashed); instead the leading one carries 54%, and 39% of the total lies in the six-dimensional span of $\partial R/\partial \theta$ against a 3% chance level. Right: the autocorrelation of the qSLS fit residual before and after whitening by the hierarchical covariance (17), with the white-noise band shaded. If the correlation were caused by variation between bubbles, whitening would flatten it into that band. It removes about a third and leaves the rest, so the remainder is structure the model does not contain.

Which precision χ^2/N is measured against. The same computation exposes a factor of $J = 18$ in the meaning of the headline number. The data is the *mean* of 18 trials, but s_i is the spread *between* trials, and the standard error of the mean is smaller by $\sqrt{18} = 4.24$. From the identical residual,

$$\chi^2/N = 0.974 \text{ against the trial spread,} \quad \chi^2/N = 17.54 \text{ against the standard error of the mean.}$$

Both are meaningful, and they answer different questions. *The model reproduces the record to within the scatter between individual experiments* is true, and is the claim this document makes. *The model is statistically adequate* is false: against the precision the 18-trial mean actually carries, it is off by a factor of seventeen. The noise-scale marginalization of Section 3.2 absorbs the difference – the implied $\beta \approx 0.24$ lies inside its prior – so the evidence ranking is undisturbed. What changes is what a residual near one entitles one to say.

What lag-one does and does not measure. The inference above – that whitening removes a third of the correlation and the remainder is structure the model lacks – rules out variation between bubbles, and nothing more. Lag-one autocorrelation at $N = 201$ samples is close to a measure of how much of a residual is *smooth*, not of what made it smooth: sampled at this density, white noise gives 0.04, a single sine period gives 1.00, a smooth random curve gives 0.999, and a mixture that is 80% smooth gives 0.944. A value of 0.918 says the residual is roughly three-quarters smooth structure. It does not say whose.

That matters because the trial deviations from the mean – pure measurement variation, with no model fitted at all – carry lag-one 0.859 (median over the eighteen trials, range 0.725 to 0.890). Most of the smoothness the fit residual shows is already present in the data before any model is involved. Whitening by the hierarchical covariance removes the part of it that lies along $\partial R/\partial \theta$, which is why it removes only a third; the rest is smooth in the data for reasons the parameter sensitivities cannot represent, and model-form error is one candidate among several rather than the established remainder.

The searches of Section 5.4 were run on the stronger reading, and their negative results are consistent with the weaker one.

5.4 What to enrich, and how it would have to be judged

The previous section leaves a specific defect: the residual carries structure the model does not contain, and it is not accounted for by variation between bubbles. The natural suspect is the assumption of a *single* relaxation time, which is strong for a crosslinked biopolymer whose relaxation is in reality distributed. Two enrichments follow from that suspicion, and they are not the same claim.

A second timescale. `TwoModeQuadraticZener` adds a second Maxwell arm sharing the elastic equilibrium, with a weight w splitting both the elastic target and the viscous forcing,

$$\dot{Z}_1 = -\frac{Z_1 - (1-w)Z_e}{\text{De}_1} + \frac{(1-w)\Phi}{\text{De}_1}, \quad \dot{Z}_2 = -\frac{Z_2 - wZ_e}{\text{De}_2} + \frac{w\Phi}{\text{De}_2}, \quad (18)$$

where Φ is the forcing the one-mode law already carries. Splitting *both* terms is what makes $w = 0$ exact: the second memory is then driven by nothing, decays from zero, and stays there.

A timescale that moves. `CarreauZener` keeps one arm and lets its relaxation time depend on the shear rate. A Maxwell arm is a spring and a dashpot in series, so $\lambda = \eta/G$; if the dashpot obeys Carreau rather than Newton,

$$\text{De}_{\text{eff}} = \text{De} [1 + (\Lambda\dot{\gamma})^2]^{(n-1)/2}, \quad (19)$$

and the arm relaxes faster the harder the medium is sheared. A collapse spans decades of shear rate, so this is a genuinely different claim from (18) about the same residual. Both terms of the memory equation carry De_{eff} , since an arm has one time constant; at $n = 1$ the bracket is unity at every shear rate and the law is identically the one-mode model.

Why the grid cannot judge either. Both carry six free parameters, and the quadrature used throughout is a Cartesian product costing count^p. At the 12 per axis used throughout, six axes is 5 971 968 solves against 168 072 for the entire standard set. The remedy is to expand about a fit rather than quadrature over a grid, at $1 + 2p$ solves – but doing so exposes a defect in the expansion itself.

The Occam factor must be capped at the prior. Written as in (5), the Laplace evidence contains $-\frac{1}{2} \log \det J^T J$. A direction the data does not determine sends an eigenvalue of $J^T J$ to zero and that term to $+\infty$: the expansion *rewards* a model for a parameter its design cannot see. This is not a small correction. On synthetic data generated from the one-mode model, the two-mode model scores

$$+29.7 \text{ nats above the one-mode model at } w = 10^{-3}, \quad -2.6 \text{ at } w = 0.3,$$

so it wins precisely where its second arm does nothing and loses only where the arm does real work. The cause is the fitted Gaussian extending far outside the bounded cube the prior occupies. Capping each eigendirection’s contribution at unity – a posterior cannot be wider than the prior it came from, Section A.7 – returns -0.0000 , -0.0004 , -0.033 and -6.81 at $w = 10^{-3}, 10^{-2}, 0.05, 0.3$: monotone, and never paying for what the data cannot resolve. The correction is a strict generalization, agreeing with the plain form to round-off wherever every direction is already sharper than the prior.

The answer, on the 15 °C record. Both were fitted by multistart in the prior’s unit coordinates, scored by the capped expansion, and summed over the modes the multistart found.

model	p	χ^2/N	$\log Z$	vs. qSLS	lag-one ρ	N_{eff}
qSLS	4	0.962	529.26	–	0.918	10.3
qSLS2	6	0.950	531.03	+1.78	0.918	7.2
qSLSthin	6	0.922	532.05	+2.79	0.875	8.2

The one-mode χ^2/N of 0.962 reproduces Section 5.2 exactly, by a different optimizer in different coordinates, which is the check that the fits are comparable at all.

Both enrichments are preferred, and neither margin means what it appears to. The residual autocorrelation is the defect they were reached for, and it does not move: 0.918 unchanged for the second relaxation time, $0.918 \rightarrow 0.875$ for the rate-dependent one, against N_{eff} near 8 out of 201 either way. Both $\log Z$ and χ^2/N presume independent residuals, so the likelihood overstates its own information by roughly $N/N_{\text{eff}} \approx 25$; deflating a 2.79-nat margin by anything of that order leaves nothing. The second arm is not idle – it lands at 16% of the memory with a timescale 15.7 times the first – it simply does not address what is wrong. And qSLSthin pins its crossover at the bottom of its range, so that margin is bound-limited and the crossover is not resolved by this record at all.

What this says. A richer relaxation spectrum is not the missing physics, or at least not the part that matters here. Two independent enrichments, each reducing exactly to the one-mode law and each free to switch itself off, both decline to and both leave the correlation in place. That is evidence about where to look next – the residual is concentrated in the first collapse, where sphericity and the far-field boundary are least secure – and it is more useful than a small positive margin would have been.

6 The bubble-dynamics operator

Every comparison above varies the material and holds the bubble-dynamics equation at Keller–Miksis. That is an assumption. With the material at its fit, changing only the operator moves the trace by four to fourteen times the median noise, which exceeds any constitutive difference measured here.

The operators are not candidate materials, so they are compared differently. We hold the candidate fixed and vary the forward solve. The parameter space is then identical across the set, the Occam terms cancel, and the difference in $\log Z$ is a Bayes factor between operators.

6.1 What the operators are

The set is a product of two choices rather than a list of equations, and reading it as a list hid a defect. The enthalpy forms share one equation: they differ only in which equation of state supplies the wall enthalpy and whether the sound speed is the constant c_∞ or the local wall value. The name *Keller–Miksis* was doing double

duty, standing for both the pressure form and the constant-sound-speed enthalpy form, which are different equations.

Separating the axes gives four dynamics that need an equation of state and two that do not:

dynamics	order	closure
Rayleigh–Plesset	incompressible	none
Keller–Miksis	$O(M)$, pressure form	none
Keller enthalpy	$O(M)$, enthalpy form, $\lambda = 0$	Tait, Mie–Grüneisen or NASG
Herring	$O(M)$, enthalpy form, $\lambda = 1$	Tait, Mie–Grüneisen or NASG
Gilmore	Kirkwood–Bethe, local c	Tait, Mie–Grüneisen or NASG
Lezzi–Prosperetti	$O(M^2)$, implicit in $\ddot{R}$	Tait, Mie–Grüneisen or NASG

Fourteen operators, of which six were available when the results below were computed. Keller enthalpy and Herring are the $\lambda = 0$ and $\lambda = 1$ members of the one-parameter family of Prosperetti and Lezzi [6], not two theories; NASG [7] adds the covolume Tait lacks and reduces to Tait exactly at zero covolume.

The second-order equation, and two typos in reading it. Equation 8.7 of Lezzi and Prosperetti [8] is the only member here that is not first order in the Mach number, and the only one implicit in the acceleration: an $R^2 \ddot{R}^2/c^2$ term makes it quadratic, so it is solved rather than divided, on the branch that stays finite as $c \rightarrow \infty$. It is used at the authors’ own recommended $(\lambda, \theta) = (0.5, 0)$.

A secondary source we worked from first prints two errors in the pair, and both were caught before implementation — the first because $\lambda = 0$ must reduce to the Keller form, the second because the term multiplying $\dot{h}_B$ is dimensionally impossible as printed. Neither is a criticism of that paper so much as an argument for reading the source: coefficients are exactly the thing a transcription loses.

The same equation carries a group of $O(M^2)$ far-field terms that vanish only for a steady drive. This implementation drops them and *refuses* a time-varying one, rather than quietly losing the order the equation exists to supply.

Validating a coefficient no asymptotic argument reaches. Members of a family agree to one order beyond the family’s accuracy, so varying λ or θ tests only the terms they multiply — and the constants 14/5 and 16/15 multiply neither. With no compressible reference solver available, the gate is direct: take the acceleration the solver returns, substitute it into 8.7 transcribed independently, and require the residual to vanish. It does, to 10^{-11} , and six mutations of the coefficients each break it.

That gate exists because a weaker one passed. The first check on the first-order family — that its members agree to $O(M^2)$ — gave the right ratios and survived a deliberate error, since members agree at that order for *any* constant in the $\ddot{R}^2$ coefficient. The test that works compares against the independently written pressure form, which has no free constant in it, and it needs the sound speed raised together with the equation of state or the two forms describe different liquids.

The prior box sets the answer. Scored with the bounds of Section 3.4, Keller enthalpy/Mie–Grüneisen ranks first at +4.02 nats and Gilmore/Tait second to last at −27.66. Three of the six fits sit on $g = 10^2$ or $\lambda_1 = 10^{-7}$, their own floors. Widening the box to $g \in (10^0, 10^6)$ and $\lambda_1 \in (10^{-9}, 10^{-2})$ reverses the ranking: Gilmore/Tait leads at +21.93 and Keller enthalpy/Mie–G falls to +7.32.

Widening moves the pinning rather than removing it. Five of six fits then sit on $\alpha = 10^3$ with g collapsed to 1.1 Pa to 3.5 Pa. Figure 26 shows the mechanism: the optimizer slides along the $g\alpha$ valley until it meets an edge.

Identified coordinates. Fixing g/α and fitting the product $g\alpha$ removes the pinning entirely, with none of 54 fits on a bound. We repeat at three ratios spanning two decades and on all three records. An ordering counts as settled when one record decides it by more than a nat and none contradicts it.

ordering	15 °C	23 °C	33 °C
compressible > Rayleigh–Plesset	+162 to +182	+74 to +79	+74 to +75
Gilmore/Tait > Keller–Miksis	+17.1	+4.2	+1.2
Keller enthalpy/Tait > Keller–Miksis	+5.8	+2.0	
Keller enthalpy/Mie–G > Keller–Miksis	+4.5	+1.5	

Twelve of the fifteen pairwise orderings are settled. Compressibility is required on every record. The pressure form assumed by every candidate in this package is beaten by three separate operators, and by Gilmore/Tait on all three records.

Under the likelihood the residuals have, that ranking dissolves. Every margin above assumes independent samples, and Section 14 deflates such margins by $N/N_{\text{eff}} \approx 20$. Applied here that puts Rayleigh–Plesset at -4.0 and -3.8 on two records — inside the five nats (47) calls live — while the conclusions call compressibility the most robust statement in this work. Both cannot stand, and the scalar is the wrong instrument for deciding which: it is derived for a sum of correlated terms and applied as though every model difference had the same shape, which Section 12 measures they do not.

So the evidences are recomputed with Σ in the likelihood — one exponential covariance per record, shared by every operator, since evidences taken under different covariances differ by $\log |\Sigma|$ and are not a Bayes factor at all. The correlation length is swept, because whitening amplifies fine structure by roughly $1/(1 - \rho^2)$ and a single ρ is a single arbitrary amplification.

15 °C, nats vs. the best	independent	$\rho = 0.8$	$\rho = 0.9$	$\rho = 0.95$	fitted
Rayleigh–Plesset	−185.7	− 4.3	−5.6	−8.5	−5.1
Keller–Miksis	−20.8	−0.15	−0.19	−0.29	−0.17
Keller enthalpy/Tait	−14.6	−0.14	−0.18	−0.29	−0.17
Gilmore/Tait	−2.2	0	0	0	0
Gilmore/Mie–G	0	−0.15	−0.20	−0.31	−0.18

Two things change and one does not. *The compressible operators become indistinguishable*: they span 0.31 nats at 15 °C and 0.33 at 23 °C, against the 17.1 and 4.2 the independent likelihood reports. Whatever separated them was information the samples did not carry. And *compressibility itself sits at the threshold rather than far above it*: Rayleigh–Plesset lands between -3.3 and -9.2 across the two records and the swept ρ , crossing the five-nat line depending on which ρ is taken.

What does not change is the sign. No correlated fit prefers the incompressible model, and Gilmore remains at or within a fifth of a nat of the top everywhere. The defensible statement is therefore narrower than the one above: *compressibility is preferred on every record and decisive on none of them at 15 or 23 °C, and the six operators are not ordered by these data at all*.

Section 17.1 sets 33 °C aside rather than reporting it: there Rayleigh–Plesset lands at -10^4 while two compressible operators separate by 200 to 550 nats, out of family with both other records by three orders of magnitude, which is the signature of an ill-conditioned covariance and not of physics.

A search budget produced an earlier answer. At six multistart restarts the same comparison placed Gilmore/Tait fourth on two records and first on the third, and reported the operator as undetermined. It also settled no ordering at 33 °C, which we read as a record without discriminating power. At ten starts the 33 °C fits reach $\chi^2/N = 0.42$ where six starts found 1.151.

Every operator had been held in the same poor basin. A record that cannot decide and a search that has not converged produce the same output. Only a better search separates them.

The initial radius is not exact. Every fit above holds R_{eq} at its inferred value, which asserts that it is known exactly. It is not: R_{max} is read off the images, but R_{eq} is inferred, and the margins in the table are small enough that this matters. Perturbing R_{eq} alone and projecting off the material span, as in Section 7, an error of 1.68 % leaves the same residual as replacing Keller–Miksis with its Mie–Grüneisen enthalpy form.

That is not a license to ignore the ranking. The two remainders lie at 58.4°, so an initial-radius error and an operator change are separable in principle – an experiment can tell them apart, and Section 7 shows the




Figure 14: The size of the operator result, against the size of an error bar this work set to zero. Both arrows are what survives refitting the material – the part of a perturbation that lies outside the shaded span, and so the only part any experiment can see. They are drawn at their measured length and their measured separation. A 1.68 % error in the inferred equilibrium radius leaves exactly as much residual as replacing the bubble-dynamics operator does. The 58.4° between them is the reason this is a call to fit R_{eq} rather than to abandon the ranking: at that angle the two are separable in principle, and Section 7 confirms the initial state absorbs under 5 % of the operator difference.

initial state absorbs under 5 % of the operator difference. What it means is narrower and worse: a quantity we set to zero is the size of the effect being reported. The remedy is to fit R_{eq} rather than assert it, which Section 8 does.

The perturbation is superlinear – the residual per unit fractional error runs 79, 93, 138 across half, one and two percent – so 1.68 % is solved for by re-solving rather than scaled from any one of those rows. Read linearly off the 1 % row it would come out a third larger.

7 Separability of the model axes

With the constitutive law, the operator and the thermal treatment all uncertain, the question is not which experiment discriminates but whether the axes are separable at all. They need not be, in two ways. A difference lying in the span of $\partial R/\partial \theta$ is reproduced by refitting the material, and is then invisible at every design (Figure 21). And two axes whose remainders are nearly parallel move the evidence together, so no design can say which moved it.

axis	size	after refit	absorbed	+ initial state
dynamics (KM → Keller enthalpy/Mie-G)	8.89	1.98	77.7%	1.89
constitutive (one → two modes)	14.42	8.14	43.5%	7.72
thermal (cold → bubble + medium)	15.99	8.46	47.1%	7.80

in units of the record’s noise. The last column widens the refit span to include R_0 and R_{eq} , which are held at their measured values everywhere else in this work. They take a further 4.7, 5.2 and 7.8 % of what the material left, so none of these differences is initial-state freedom in disguise. A near-zero number here is also what a broken projection would report, so the operation is checked both ways on the same vectors: handed the difference itself the basis absorbs it to 5×10^{-15} , handed a random column it absorbs 0.02 of 1.98.

The remainders sit at 46, 71 and 38° to one another. No pair is confounded, so the design problem is well posed for all three. Two things follow that were not expected.

Thermal is the *largest* lever, not a negligible one. It moves the trace most and survives refitting most. So the earlier observation – that switching it on made χ^2/N slightly worse – says the direction it moves in is not the one the record wants, not that it is small.

The operator pair measured here is the most absorbed of the three, and that is the mechanism behind Section 6: most of *this* operator change can be mimicked by adjusting the material.




Figure 15: Turning a model choice into a parameter. Writing $R(\theta, \varepsilon) = (1 - \varepsilon)R_A(\theta) + \varepsilon R_B(\theta)$ gives $\partial R / \partial \varepsilon = R_B - R_A$ at $\varepsilon = 0$, so the difference between two models becomes one more column of the Jacobian. Discrimination and estimation then live in a single information matrix, and D -optimality over the augmented set balances learning the material against learning which model produced the trace. Nothing about the criterion changes, so the certificate still applies. The variance of ε after the material is fitted out is what says whether a design can tell the models apart at all.

It does not generalize to the axis, and the difference matters because it was read as a property of operators. Absorption is a property of a *pair*, and the pair above is the closest one available at the time. Measured against Keller–Miksis on the same record, with the same projection, the six dynamics of Section 6.1 span the range rather than clustering at its top:

against Keller–Miksis	size	after refit	absorbed
Keller enthalpy/Mie–G	8.89	1.98	77.7%
Keller enthalpy/Tait	12.85	5.81	54.8%
Herring/Tait	34.49	24.80	28.1%
Gilmore/Tait	39.30	29.33	25.4%
Lezzi–Prosperetti (2nd order)/Tait	53.21	42.83	19.5%

The second-order equation leaves 42.8 noise units where the pair this section was built on leaves 1.98 — twenty-two times as much, and four fifths of it visible to the data rather than one fifth. So the operator axis is not uniquely hidden; the two operators available when that claim was made happened to be the two hardest to tell apart.

The peak wall Mach number on this record’s own geometry is 0.110, so $O(M^2)$ is near 1.2% and a second-order correction is not a refinement — it is the largest operator difference measured here. One caution on reading the column: it is an L^2 norm over the whole record, so it is dominated by how far the trajectories decohere near collapse rather than by a pointwise $O(M^2)$ magnitude. It is the right yardstick against the other entries and the wrong one for a physical size.

A design against all three. Make each axis a parameter through $R(\theta, \varepsilon) = (1 - \varepsilon)R_A + \varepsilon R_B$, so $\partial R / \partial \varepsilon = R_B - R_A$ is one more column of J . This puts discrimination and estimation in one information matrix and leaves the criterion concave, so the certificate of Figure 17 applies unchanged. The information is averaged over a decade of $g\alpha$, because operator information is governed by collapse depth and a measure certified at one material misranks others. The measure certifies at a gap of 10^{-9} on four support points.

axis	variance at the optimum	at the 15 °C geometry	efficiency
dynamics	6.78×10^{-3} (binding)	9.91×10^{-3}	68.4%
constitutive	5.45×10^{-4}	2.24×10^{-2}	2.4%
thermal	4.40×10^{-4}	1.05×10^{-2}	4.2%

Reported per axis rather than as one determinant. A design maximizing det could buy its whole score on the two easy axes and leave the operator undetermined without saying so. The experiments performed are near-best for the hardest axis and 24 to 41 times off for the two easiest. So a change of geometry buys a great deal of constitutive and thermal discrimination at little cost to the operator. The support wants $R_{\max}$ near 60 μm at high stretch and near 1200 μm at low stretch, against the 277 μm and stretch 7.09 performed.




Figure 16: Three choices go into every prediction, and they are made independently: the constitutive law, the bubble-dynamics equation, and whether heat transfer is modeled. Published comparisons vary the first and leave the other two at the origin. Some of each change can be canceled by refitting stiffness and viscosity, which makes it invisible no matter how the experiment is run; what remains is 22% of an operator change, 57% of a constitutive change and 53% of a thermal one, and no two of those remainders point in similar directions. All three are therefore distinguishable in principle. The 77.7% is the CLOSEST pair of operators rather than the axis: across the six dynamics of Section 6.1 absorption runs from there down to 19.5%, and the second-order equation leaves twenty-two times as much as the pair drawn here.

8 Fitting the initial radius

Section 6 reports operator margins of a few nats while holding R_{eq} fixed, and a 1.68% error in R_{eq} is worth as much as the operator change those margins measure. A quantity that large cannot be asserted. So we fit it, as a nuisance parameter with a prior. The question is not whether the evidence moves – adding a parameter always moves it – but whether the *ordering* does. An operator preferred by 17 nats with R_{eq} pinned, and not preferred once it floats, was never an operator result.

The prior width is the whole argument, and nothing measures it. Too wide and R_{eq} absorbs the operator difference, which reads as “the operators are indistinguishable” while being a statement about the box. Too narrow and the pinned answer is reproduced by construction. We therefore sweep the half-width over 3% to 25% rather than choose one. A conclusion that holds across that range is a conclusion; one that flips inside it is a prior.

A convergence gate with no tuning constant. Every wider box contains every narrower one, and all of them contain R_{eq} at its inferred value, which is the pinned fit. The best attainable χ^2/N can therefore only fall as the width grows. A cell that rises has not found its own optimum. This matters because it caught a real failure: at ten multistart restarts, five of 72 cells failed it, one reporting -117 nats between a $+13$ and a $+7$ – which reads as a prior effect and is a search that stopped early. At 24 restarts two cells fail, and both are excluded below rather than read as physics.

operator	15 °C		23 °C		33 °C	
	pinned	$\pm 25\%$	pinned	$\pm 25\%$	pinned	$\pm 25\%$
Rayleigh–Plesset	-165.0	-178.6	-76.9	-81.8	-74.4	-74.2
Keller–Miksis	0	0	0	0	0	0
Keller enthalpy/Tait	$+6.1$	$+0.8$	$+2.1$	$+0.1$	$+0.8$	$+0.8$
Gilmore/Tait	$+18.5$	$+5.0$	$+4.3$	$+0.5$	$+1.9$	-0.0
Keller enthalpy/Mie–G	$+4.7$	$+0.3$	$+1.6$	$+0.1$	$+0.6$	$+0.9$
Gilmore/Mie–G	$+20.7$	$+11.2$	$+4.3$	—	$+1.1$	-0.3

nats against Keller–Miksis; “—” marks the one cell the gate excluded. Of 17 orderings the pinned fit called

decisive, 15 stay decisive and keep their sign at every width. None reverses. Two fall below five nats at some width, both at 15 °C.

The conclusions of Section 6 therefore survive, but not equally. *Compressibility is required* at every width and on every record, by 74 to 179 nats – the most robust statement in this work. *Gilmore beats the pressure form* at 15 °C, still by 5 to 11 nats with R_{eq} free. But at 23 °C and 33 °C every margin above Keller–Miksis collapses to under a nat. Those two records never had operator discrimination; pinning R_{eq} is what made it look as though they did.

The data want a larger equilibrium radius. The fitted scale is the same story told forwards, and it is the most consistent number in this study. At $\pm 3\%$ every one of the 18 cells pins against the upper edge. Given room, they agree closely: 1.104 to 1.115 at 15 °C, 1.074 to 1.086 at 23 °C, and 1.032 to 1.040 at 33 °C, across six operators and two prior widths.

So R_{eq} is inferred about 3 % to 11 % too small, and the fit says so whichever operator it is asked through. The residual improves accordingly — χ^2/N falls from 0.97 to 0.62 at 15 °C, 1.03 to 0.90 at 23 °C, and 0.44 to 0.38 at 33 °C. That the offset shrinks as the gel warms is a pattern we can measure but not yet explain, and it is larger than the 1.68 % that makes R_{eq} worth as much as the operator choice.

Where it actually wants to sit

The sweep above asks whether a conclusion survives letting R_{eq} float. It never asks where R_{eq} goes, and the answer is not the stored value. Fitting it on the mean trace of each record over a box wide enough that nothing is cut off:

record	stored stretch	implied	offset	χ^2/N	lack of fit
15 °C	7.09	6.40	+10.8%	0.971 $\rightarrow$ 0.632	16.79 $\rightarrow$ 8.80
23 °C	7.37	6.80	+8.3%	1.029 $\rightarrow$ 0.901	2.95 $\rightarrow$ 2.15
33 °C	6.83	6.59	+3.6%	0.439 $\rightarrow$ 0.379	1.80 $\rightarrow$ 1.49

Every record prefers a larger equilibrium radius, by three to eleven percent against the 1.68 % this section opens by calling worth an operator change.

Read against the source, most of that is not an offset. The stretch is not a single measurement. Abeid et al. [9] tabulate it as a mean over the experiments in each bin, with a spread: 7.09 ± 0.36 over 18 events, 7.37 ± 1.28 over 14, and 6.83 ± 0.49 over 7. Against those the preferred values sit at 1.9, 0.45 and 0.49 standard deviations. Only 15 °C is outside the tabulated uncertainty at all, and it is marginal.

The definition matches too, which was the other thing worth checking. That source defines R_{∞} as the equilibrium bubble-wall radius — the quantity the solver wants — so the ratio is not a different measurement pressed into service, and there is no unit or convention error to correct.

So the honest reading is not that the stretch is wrong. It is that a *population mean is being applied to every trial*, and the population is wide: the same table reports R_{max} at 277 ± 48 , 298 ± 59 and 312 ± 32 μm , so individual bubbles differ by ten to twenty percent in the absolute scale that sets the Reynolds, Weber and Deborah groups. Every fit in this document uses one value for all of them.

Two consequences follow. The per-trial spreads of Section 5.3 — 1.9, 6.7 and 3.1 percent in R_{eq} — are *smaller* than the scatter the source reports for the same quantity, so they are consistent with it rather than evidence of anything new. And the absolute R_{max} of each event, which varies by more than the ratio does, is not fitted anywhere here and is not recoverable from the traces, since each is normalized by its own maximum before it reaches us.

What must be said plainly is what the reported parameters rest on. Freeing R_{eq} moves μ by 11 to 23 percent and $g\alpha$ by 9 to 41, and it moves λ_1 by a factor of *five and a half* at 15 °C. Those are the numbers this document reports, and they are conditional on a stretch known only to ± 5 to ± 17 percent.

9 Scoring the thermal treatment

Section 7 finds the thermal treatment the largest of the three model axes: it moves the trace by 16 noise units and keeps 8.5 after the material absorbs what it can. Scoring it means running the comparison of Section 6 with the thermal treatment varied and the material axes held identical, so the Occam terms cancel and the difference is a Bayes factor between physics rather than between parameter counts.

The first attempt failed, and how it failed was diagnostic. At ten multistart restarts and again at twenty-four – a $2.4\times$ change of budget – the 23 °C rows moved by at most 0.01 nats while the others moved by 15, 153, 19 and 68. Decisively, *more restarts fitted worse*: at 33 °C bubble + medium went from $\chi^2/N = 0.428$ to 1.073. Best-of-24 cannot be worse than best-of-10 at a converged optimum, so the search was landing in different basins rather than refining one, and a third increase of the budget was not the remedy.

The remedy was a better start. Each thermal fit is now seeded from its own record’s converged cold optimum instead of sampling a four-dimensional box afresh (`docs/writeup/thermal.py`), at twenty-four restarts. That run takes 2.7 h on six workers and recovers what the cold-started search had lost: 33 °C bubble + medium returns to 0.428, and 15 °C bubble + medium improves by 15.8 nats.

It also loses a basin the earlier run had found. At 15 °C the *bubble* treatment lands 15.0 nats worse warm-started than cold-started, because seeding from the cold optimum is a good start for a treatment close to cold and a bad one for a treatment that is not. So this is not a converged search either; it is a search whose failures have moved. Both runs are minimisations of the same objective, so the table below reads best-of-both, which is valid and is what a third run would be compared against.

record	cold	bubble	bubble + medium
15 °C	0	+8.6	+21.6
23 °C	0	+2.7	+8.0
33 °C	0	−5.0	+1.7

nats against the cold model. The bubble + medium column is positive on every record and is the same number in both runs at 23 °C and 33 °C, so it is a property of the data rather than of the optimiser. The bubble column changes sign across records and moved by 15 nats between runs at 15 °C; it is search noise and we decline to read it.

What the score is worth

Read raw, +31.2 nats combined is overwhelming. It is not, and Section 14 says why: these margins come from a likelihood that treats 201 samples as 201 independent observations, and the residuals of these very fits have lag-one autocorrelation between 0.907 and 0.962. Deflating each record by its own AR(1) effective sample size, $N_{\text{eff}} = N(1 - \rho)/(1 + \rho)$:

record	raw	lag-one	N_{eff} of 201	deflated
15 °C	+21.57	0.915	8.9	+0.96
23 °C	+8.01	0.962	3.9	+0.16
33 °C	+1.66	0.907	9.8	+0.08
combined	+31.24			+1.19

The records are independent, so the deflated margins add. A Bayes factor of 3.3 is substantial on Jeffreys’ scale and an order of magnitude short of the five nats Section 14 requires before calling a question closed. The 23 °C record, whose fit was the most stable of the three, is inflated 52-fold and contributes least.

The conclusion is therefore the same as the first attempt’s and rests on nothing the first attempt could see. The thermal treatment is favored – consistently, on every record, by the one column that is stable under both a change of optimiser and a change of budget – and it is not established. What separates those two statements is not more restarts. It is 1.19 nats against a threshold of five, which is a statement about how much data of this kind is worth, and it is the quantity Section 13 designs against.

10 What the model error costs

Every comparison to this point — constitutive, operator, initial radius, thermal — has been made between models that Equation (16) rejects. That does not make the comparisons worthless, since a ranking among wrong models is still a ranking, but it leaves a question no χ^2 answers: how much of a reported parameter is physics, and how much is the model being the wrong shape? The question has an answer, and it is not the one an error bar gives.

First, whether the ranking survives being wrong, which is testable and was not tested. “A ranking among wrong models is still a ranking” is a claim. Under misspecification the evidence rewards whichever model best ABSORBS the discrepancy, and absorption is precisely the mechanism (21) below shows biases the parameters — so the ranking could be measuring absorption capacity rather than physical closeness, and nothing separates those.

It separates directly. Generate from a truth the catalogue does not contain — the two Section 15 uses, thermal transport and a second relaxation mode — rank the catalogue by evidence, and separately measure which candidate is genuinely closest, defined as the residual its OWN best fit leaves against the noiseless truth.

candidate	thermal truth			two-mode truth		
	log Z margin	rank	distance	log Z margin	rank	distance
qSLS	0	1	0.545	0	1	0.191
SLS	−73.0	2	1.077	−44.1	2	0.803
NHKV	−2549	3	4.974	−2314	3	4.698
qKV	−2598	4	5.039	−2405	4	4.809

The orderings are identical: rank correlation +1.000 under both truths, and the evidence winner is the closest model in both. The demanding part of that is the bottom pair, whose distances differ by 1.3% and which the evidence still orders correctly.

Two limits on what this licenses. Both truths are drawn from physics this document already screens, so it tests misspecification of a KIND already considered and of a size Section 7 measures at 14 to 16 noise units. And the catalogue’s tiers are separated by thousands of nats, so the test is not stressed where it would be most informative — between rivals a few nats apart, which is the regime Section 14 says the operator axis is actually in. What it does establish is that the defence above is not merely an assertion at the size of error these records show.

Half of it is invisible, and that is a theorem

Write the truth as $y = m(\theta) + \delta + \varepsilon$. Whitening by the standard error of the mean — the $\sqrt{J}$ of Equation (16), not the trial spread — and letting J hold the parameter sensitivities, the residual splits along the model’s own span,

$$d = \underbrace{Pd}_{\text{absorbable}} + \underbrace{(I - P)d}_{\hat{\delta}}, \quad P = J(J^\top J)^{-1}J^\top. \quad (20)$$

At a converged interior fit the normal equations give $J^\top d = 0$ exactly, so $Pd = 0$ and $\hat{\delta} = d$: the whole residual is identifiable discrepancy, and the component of δ lying in the span of J has left *no trace whatsoever*. It was absorbed into $\hat{\theta}$ while fitting. Two worlds — a biased θ with no discrepancy, and the true θ with a discrepancy in the span — predict the same data exactly. This is the unidentifiability of Kennedy and O’Hagan [10], and it is why the bias cannot be estimated from these data at any budget.

So bound it

Suppose only that the invisible part is no larger than the visible one, $\|\delta_\parallel\| \leq B$. The induced bias is $\Delta\theta = (J^\top J)^{-1}J^\top \delta_\parallel$, and maximising each component over that ball gives

$$\max_{\|\delta_\parallel\| \leq B} |\Delta\theta_k| = B \sqrt{[(J^\top J)^{-1}]_{kk}} = B \sigma_k, \quad (21)$$

since $\|J(J^\top J)^{-1}e_k\|^2 = [(J^\top J)^{-1}]_{kk}$. The worst bias is B multiples of each parameter's *own* standard deviation, the same multiple for every coordinate, so a single number covers the whole vector. Taking $B = \|\hat{\delta}\|$ is the natural choice and is not conservative: nothing in the data forbids the unseen component being larger than the seen one.

The bound exists only in the identified coordinates

Equation (20) means something only where $Pd = 0$, and in the natural axes that can never hold. Section 3.5 shows the likelihood depends on $g\alpha$ alone; measured at the fitted point, g and α are anticorrelated at -1.00000 with $J^\top J$ conditioned near 10^8 and a null direction of $(-0.707, 0, 0, +0.708)$ in log coordinates. A fit slides along that valley until it meets a wall of the prior box, and at a *constrained* optimum the gradient along the active bound does not vanish, so part of the residual stays absorbable.

Widening the box does not help, which is worth stating because it is the obvious thing to try. Released from $g \geq 100$ Pa, the pair slid until α reached its own upper bound instead: the pin moved rather than lifted, and $g\alpha$ was preserved to 1.6% across a hundredfold change in g . A box has walls, and a fit on a flat valley finds one.

Refitting in the identified coordinates $(\mu, g\alpha, \lambda_1)$ removes the valley, and with it the obstruction:

coordinates	cond $J^\top J$	absorbable	at optimum	bound
$(\mu, g, \lambda_1, \alpha)$	9×10^5	39% to 59%	no	unavailable at any box
$(\mu, g\alpha, \lambda_1)$	3×10^1	0.0%	yes	(21) applies

The budget

record	bound	μ	$g\alpha$	λ_1
15 °C	59.3σ	$\times 1.58$	$\times 1.30$	$\times 3.11$
23 °C	52.6σ	$\times 2.00$	$\times 1.55$	$\times 3.90$
33 °C	24.7σ	$\times 1.54$	$\times 1.57$	$\times 2.98$

Read as a model-form error budget: the identified modulus could be wrong by 30% to 57%, the viscosity by 54% to 100%, and the relaxation time by a factor of three to four, from model-form error alone, with no amount of data of this kind able to distinguish that from the truth. The large multiples of σ and the modest factors are consistent, and their ratio is the point: σ is small in these coordinates precisely because they are the identified ones, which is what makes the budget readable rather than infinite.

What could remove it

The bound says how much of a parameter the discrepancy could be eating. It does not say what the discrepancy is, and $\hat{\delta}$ is not a shapeless residual: the three records' $\hat{\delta}$ correlate at 0.49 to 0.84, where unrelated curves of this length would sit near 0.08, and between 65 and 69 percent of each sits in the first collapse. One curve, measured rather than guessed, is a thing a candidate physics can be screened against.

The screen is a projection, not a fit. Any enrichment supplies a direction v — the trace it would add, differenced against the current model — and only the part of it orthogonal to the existing sensitivities can remove any of $\hat{\delta}$. The rest is absorbed by refitting the parameters already present, which improves χ^2 and explains nothing. So the question is a cosine,

$$\text{removable} = \cos^2((I - P)v, \hat{\delta}), \quad \cos = \frac{\langle (I - P)v, \hat{\delta} \rangle}{\|(I - P)v\| \|\hat{\delta}\|}, \quad (22)$$

at one solve per candidate rather than a multistart and an evidence integral each. That inversion is the point. Fitting every candidate answers “which of these fits best”, which among models Equation (16) rejects is the wrong question; (22) answers “could this be the missing physics at all”, and a candidate near zero cannot be, whatever its Bayes factor does. Screen first, fit what survives.

The sign is not a detail. Most enrichment amplitudes are one-sided: a Maxwell arm’s share, a stiffening coefficient and a switched-on transport term are all non-negative. A candidate whose direction *anti*-aligns with $\hat{\delta}$ therefore cannot reduce it at any admissible amplitude, and scoring $|\cos|$ reads such a candidate as the most promising one on the table. That is not hypothetical — it happened here, and it is why the second relaxation arm carries a dagger below. The reachable set is the *cone* of non-negative combinations rather than the span, so the joint figure is a non-negative least squares onto that cone and not a projection onto a subspace.

candidate	15 °C	23 °C	33 °C
initial radius	23.7%	13.0%	13.9%
operator: keller-enthalpy/MG	7.7%	1.8%	3.9%
operator: gilmore/Tait	1.9%	0.4%	4.8%
thermal (bubble + medium)	2.6%	2.5%	6.5%
thermal (bubble)	1.9%	2.4%	3.6%
mass transfer	0.2%	0.2%	2.4%
second relaxation arm	1.1% [†]	58.1% [†]	3.8%
all together, on the cone	25.2%	15.1%	21.0%
the same, read as a subspace	25.9%	71.5%	21.7%
$\ \hat{\delta}\ $	59.3	52.6	24.7

[†] anti-aligned: the cosine is negative, so no admissible amplitude removes anything. At 23 °C the cosine is -0.762 , and read as $|\cos|^2$ that candidate is the best on any record in the table at 58.1% — while in fact it can only make the residual worse. The last two rows are the cost of getting this wrong, measured: read as a subspace the 23 °C candidates jointly remove 71.5% of the discrepancy, and on the cone they remove 15.1%. The other two records move by less than a point, because there the anti-aligned candidate was small anyway — the error is not uniform, and it is largest exactly where it would have mattered most.

The list omitted the first collapse, which is where the discrepancy is. Every candidate above is a bulk constitutive, transport or configuration effect, and 65 to 69 percent of $\hat{\delta}$ lies in the first collapse — where Section 5.4 names sphericity and the far-field boundary as least secure, and then screens neither. Two first-collapse candidates, on the same cone and the same footing:

candidate	15 °C	23 °C	33 °C
asphericity $n = 2$ (silhouette)	0.4%	0.6% [†]	0.0%
asphericity $n = 2$ (volume equivalent)	0.2% [†]	2.5% [†]	5.0% [†]
asphericity $n = 3$ (volume equivalent)	0.2%	1.5% [†]	3.3% [†]
initial wall velocity +0.02	22.6%	37.6%	11.7%
initial wall velocity −0.02	33.6% [†]	28.9% [†]	19.6% [†]

[†] anti-aligned, so no admissible amplitude removes anything; the signed pair on the last two rows is one candidate screened in both directions.

The shape modes are integrated from Plesset [11] along the fitted trajectory, $\ddot{a}_n + 3(\dot{R}/R)\dot{a}_n = A_n a_n$ with $A_n = (n-1)\ddot{R}/R - (n-1)(n+1)(n+2)\sigma/(\rho R^3)$, and screened under both imaging conventions because what a shape mode does to a REPORTED radius depends on whether the instrument returns a silhouette or a volume equivalent — an assumption, so both are shown.

Asphericity is not it. At most 5%, anti-aligned on most records, and smaller than thermal transport. That is worth knowing precisely because it was the obvious suspect.

The initial condition is the largest single candidate ever screened here. Every fit in this document starts the bubble at $R_{\max}$ with zero wall velocity, which asserts that the imaged maximum is a turning point of a free collapse. A laser deposits energy; it need not be. Releasing that assumption reaches 37.6% of $\hat{\delta}$, against 23.7% for the initial radius and 6.5% for the best genuine-physics entry on the original list.

Fitted rather than screened, that 37.6% does not survive. A screen bounds what a candidate could remove with its amplitude free, and the way to collect on it is to fit. Doing so with the stretch *also* free — pinning a quantity known only to five–seventeen percent would let one error masquerade as the other — the velocity does land somewhere definite and does not buy what the screen promised:

	15 °C		23 °C		33 °C	
free	χ^2/N	lack of fit	χ^2/N	lack of fit	χ^2/N	lack of fit
nothing	0.971	16.79	1.029	2.95	0.439	1.80
R_{eq}	0.623	8.43	0.901	2.15	0.379	1.60
u_0	0.724	15.38	0.372	2.86	0.278	1.57
both	0.500	—	0.324	2.30	0.229	1.38

χ^2/N falls everywhere, which is what free parameters do and is not the question. Against *lack of fit*, adding u_0 on top of a free stretch improves one record and worsens another, and 15 °C is withheld: its three prior widths fail the nesting gate of Section 8 — a box containing another scoring worse than it — at 16 restarts and again at 32, so that surface is multimodal and the cell is not read.

Two things do come out of it cleanly. The velocity lands at -0.022 to -0.033 of the Rayleigh scale on every record, always inward, and identically at $\pm 10\%$ and $\pm 30\%$ prior width, so it is a determined quantity rather than a bound. And R_{eq} and u_0 are *separately identified*: their correlation is $+0.06$ to $+0.13$ with $J^T J$ conditioned near 10^2 , against -1.00000 and 10^8 for the g – α pair of Section 3.5. Two configuration quantities that could easily have been one direction are not.

The obvious reading of an inward velocity at the imaged maximum is that the maximum is a sampled frame rather than the true turning point. That is checkable and does not survive either: half a frame of the model’s own deceleration is -0.007 to -0.008 of the Rayleigh scale, three to four times smaller than what is fitted. The sign and the order are right and the magnitude is not, so sampling is part of it at most.

Read with Section 8, the two point the same way. The largest entry on the old list was the initial radius and the largest on the new one is the initial velocity; both are the initial condition rather than the material. The discrepancy this document has been attributing to constitutive incompleteness is, on the evidence of its own screen, better aimed at how the records begin.

What this says. Nothing on the constitutive or transport list accounts for the discrepancy. Every genuine physics candidate is small — thermal transport between 1.9 and 6.5 percent, mass transfer below 2.4, the operator below 7.7 — and taken *all together* on the reachable cone they leave between 75 and 85 percent of $\hat{\delta}$ unexplained on every record. The largest single entry is not physics at all but the initial radius, a configuration quantity that Section 8 shows moves the trace as much as the operator does, and even it removes at most a quarter.

Two cautions travel with the table. The figures are *upper bounds*, not forecasts: each is what a candidate could remove with its amplitude free and the base parameters responding linearly, and a fit obeys neither, so the delivered reduction is smaller. And a screen cannot propose what it was not given — these are the enrichments this package implements, and the 75 to 85 percent that survives is a statement about them rather than a proof that no mechanism exists. What it does establish is that the discrepancy Equation (16) detects is not the thermal, mass-transfer or operator physics already on the shelf, and that (21) is therefore the honest way to carry it rather than a placeholder awaiting the obvious fix.

Three consequences run through the rest of this paper. A parameter interval that omits (21) understates its own uncertainty by one to two orders of magnitude, so the posterior widths of Section 5.2 are not the error bars a rheologist wants. A model comparison is a comparison of the identifiable parts, since the absorbed parts of two models’ discrepancies are invisible in both. And a design criterion computed under a rejected model optimises a quantity whose parameters carry this budget — which is the gap Section 15 names and (21) finally sizes.

11 Experimental design

One assumption carries this whole chapter

Every design below is scored at geometries nobody has run, over $R_{\max}$ from 50 to 1200 μm . The records span 277, 298 and 312 μm — a twelve percent range. So the chapter extrapolates by a factor of twenty-four in the one variable it optimizes, and three separate quantities have to be carried out there with it: the noise profile σ , the correlation length τ , and the discrepancy $\hat{\delta}$.

Each is carried by *phase* rather than by clock time, t/t_c , on the argument that all three are properties of the collapse and not of the apparatus. That argument is supported. It is not established, and the distinction matters enough to state once rather than three times in passing.

What supports it is that each transfer was tested for consistency across the records, and each passed: median-filtered σ profiles bring all three records to the same recommended geometry (Section 15), and the three $\hat{\delta}$ overlap at 0.44 to 0.81 against 0.05 for unrelated curves (Section 15). Transfer by absolute time fails the same test, and fails it for a statable reason — t_c spans a factor of twenty-four across the candidates, so a fixed clock time lands at a different point of every collapse.

What that evidence cannot do is test the extrapolation actually being made. The three records differ in *temperature*, not in size. Agreement among them says the transfer is not sensitive to the material changing; it says nothing about a bubble four times larger, because no such bubble has been recorded. Everything downstream — the certified measures, the batch tables, the run budgets — is conditional on this, and the first experiment run at a genuinely different $R_{\max}$ tests it directly and cheaply.

Designing without assuming the model

Everything above optimizes the Fisher information of one model at its fitted parameters, which is circular if that model is wrong. Two checks that do not privilege it.

The record is information-rich; the parameterization is not. Draw 400 trajectories from the posterior and take the singular values of the centered ensemble. Eleven modes clear the trial noise floor of 0.018 $R_{\max}$. That is not a count of identifiable combinations: four parameters span at most a four-dimensional manifold, and the extra modes are its curvature. But the record distinguishes far more shapes than the fit extracts. The limit is qSLS, not the measurement.

Discrimination does not privilege a model. T-optimality [12] asks a different question: which design makes the candidates disagree most? The criterion is

$$T(d) = \min_{\theta_2} \|m_1(\hat{\theta}_1, d) - m_2(\theta_2, d)\|/\sigma, \quad (23)$$

and the minimization is the whole content of it. A rival that retunes its parameters to imitate has not been discriminated against. So the separation is measured against the rival’s *best imitation*, never against its own fitted values.

Two errors here inflated T , both for one structural reason. T is a *minimum*, so anything stopping short of it reports discrimination that is not there. Evaluating each rival at its own fit gave 2.69 for qSLS–SLS at the present design; re-fitting with one Nelder–Mead pass gave 0.67.

Restarting and polishing changed other entries again. At 1200 μm the reported 4.92 fell to 2.38. A 0.1% change of design moved one loose evaluation from 7.25 to 1.36 — the optimizer’s signature, not the physics. The converged values are:

design	qSLS-SLS	qSLS-qKV	qSLS-NHKV
277 μm , stretch 7.09 (present)	0.67	4.53	4.37
277 μm , stretch 5.00	0.72	4.61	4.61
277 μm , stretch 3.00	0.74	1.72	1.72
199 μm , stretch 3.55 (E-optimal)	0.56	2.59	2.59
895 μm , stretch 4.93	2.39	7.13	7.13
910 μm , stretch 5.19	1.36	6.97	6.97
1200 μm , stretch 7.09	2.38	5.03	5.63
100 μm , stretch 20.0	1.26	8.04	4.17
57 μm , stretch 19.5	1.64	5.53	5.00

At the present design SLS imitates qSLS to within 0.67 noise units, inside the measurement scatter. An unrelated calculation corroborates it. A systematic offset of 0.668σ over 201 samples contributes $201 \times 0.668^2 = 89.7$ to χ^2 , against a measured log-evidence gap of 101.6. Two computations sharing no machinery, agreeing to 12%.

These values are upper bounds, and the criterion is the reason. T is an inner *global* minimization, and that minimization is multimodal. Nelder–Mead and Gauss–Newton both converge, to different basins. At 895 μm Nelder–Mead returns 2.39 against Gauss–Newton’s 1.52; at 1200 μm the ordering reverses.

Multistart Gauss–Newton finds a lower value in 12 of 27 cells. Analytic Jacobians make it $44\times$ cheaper than the derivative-free version – 34s against 25 minutes for the table. A stationarity check from the same Jacobians reports 11 cells still not at a minimum.

Every improvement to the optimizer lowers the scores, because a better-optimized rival imitates better. So the tabulated values are upper bounds on discrimination. The true separations are smaller than any of them.

This is not a defect of the implementation but of the criterion. A minimum is attained at a point, so landing in the wrong basin gives a wrong answer with no indication that anything went wrong, and enumerating the outer design space exactly does not repair it: a dense grid over an unreliable integrand produces a front that is precisely wrong. Any criterion built on an argmin – T -optimality, profile likelihood, minimax design – inherits this.

The structural fix is to replace the minimum with an integral. Treating the model label as a discrete parameter makes discrimination an expected-information-gain problem over the augmented parameter (θ, m) , whose inner quantity is the marginal likelihood $\int p(Y \mid \theta, M, d) \pi(\theta \mid M) d\theta$. An integral accumulates over all modes instead of requiring the best one be found. Multimodality stops being a failure mode and becomes a property of the integrand: a missed mode biases the evidence slightly rather than corrupting the criterion.

It also puts discrimination and parameter precision in one framework. The cost is that the marginal likelihood is prior-sensitive where T is not. The prior becomes part of the criterion rather than a nuisance.

The criteria do not agree. Computed correctly, the criteria want different experiments. E-optimality peaks at 199 μm and stretch 3.55. Separating qSLS from SLS or from NHKV is best at 895 μm and stretch 4.93. Separating qSLS from qKV is best at 100 μm and stretch 20, near the opposite corner of the design space. At the E-optimal design the discrimination scores are the worst in the table, so the conflict is not marginal.

The reason is physical, not numerical. Telling a material with a relaxation mode from one without needs a collapse fast enough to excite it. Separating g from α needs a gentle collapse, because the term of Z_e carrying that distinction dies as λ^{-4} . No design is both fast and gentle.

There is accordingly no single best design, and a scalar design objective is answering a question that has no scalar answer. What replaces it is the *Pareto front*: the set of designs on which no other design is better on every criterion at once. Enumerating a 14×18 grid over $(R_{\max}, \lambda)$ and applying that test leaves 12 designs undominated, spanning 50–1200 μm and stretch 4–18. Reporting that set rather than a single optimum is the honest summary of an experiment serving several questions at once; `pyimr.pareto.explore_tradeoff` computes it.

The T columns entering the domination test are upper bounds, so the front is provisional in its discrimination coordinates. The E-optimality coordinate is an eigenvalue of $J^T J$ with no inner optimization, and carries no such reservation.

Discrimination as an integral rather than a minimum

Everything above scores a design by T , defined through a *global minimum* over the rival’s parameters. That definition is the trouble in the previous subsection, and the trouble is structural rather than computational. Here we replace the minimum with an integral, say why that is more robust, and report what it gives.

The model label is a parameter. Write $M \in \{M_1, M_2\}$ for the model index with prior $p(M)$, and let each model carry its own parameter θ with prior $\pi(\theta | M)$. Nothing distinguishes M from any other unknown, so the information a design d yields about it is the mutual information

$$I(M; Y | d) = \mathbb{E}_M \mathbb{E}_{Y|M,d} \left[\log \frac{p(Y | M, d)}{p(Y | d)} \right], \quad p(Y | d) = \sum_M p(M) p(Y | M, d), \quad (24)$$

the expected reduction in entropy of M – exactly as the expected information gain above is the expected reduction in entropy of θ . Discrimination and estimation are one criterion applied to different components of the augmented unknown (θ, M) . They are not competing philosophies: the earlier tension between T - and E -optimality is about *which component we care about*, not about two schools.

The quantity entering (24) is the marginal likelihood, or evidence,

$$p(Y | M, d) = \int p(Y | \theta, M, d) \pi(\theta | M) d\theta, \quad (25)$$

the same object as (4) but now at a hypothetical design and for hypothetical data. It is an integral over θ , and that single fact is what the rest of this subsection turns on.

The criterion actually computed. Rather than (24) we score a design by the expected log Bayes factor in favor of the model that generated the data,

$$U(d) = \mathbb{E}_{Y \sim p(\cdot | M_1, d)} [\log p(Y | M_1, d) - \log p(Y | M_2, d)] = D_{\text{KL}}(p(\cdot | M_1, d) \| p(\cdot | M_2, d)). \quad (26)$$

Recognizing it as a Kullback–Leibler divergence between the two prior-predictive distributions settles its properties. By Gibbs’ inequality $U(d) \geq 0$, with equality exactly when the two predictives agree almost everywhere: *a model cannot discriminate against itself, at any design*.

That is sharp and falsifiable, and it is what the implementation is tested against. Two independently drawn banks from one family must score zero; any systematic excess is bias.

Equation (24) relates by $I(M; Y | d) = \frac{1}{2} [D_{\text{KL}}(p_1 \| \bar{p}) + D_{\text{KL}}(p_2 \| \bar{p})]$ with $\bar{p}$ the equal mixture. So (26) is the same comparison read against the rival rather than the mixture – the more direct statement of “how strongly will this experiment favor the truth”.

Why an integral is robust where a minimum is not. Both criteria require an inner computation that can go wrong. The asymmetry is in how the error propagates.

For T , any optimizer returns $\hat{T} = \|m_1 - m_2(\hat{\theta}_2)\|/\sigma$ at whatever point it stopped, and since T is a minimum, $\hat{T} \geq T$ always. If $\hat{\theta}_2$ lies in the correct basin but is imprecise, stationarity gives $\hat{T} - T = O(\|\hat{\theta}_2 - \theta_2^*\|^2)$ and the error is negligible. If it lies in the *wrong basin*, the error is $O(1)$: a fixed, unbounded overstatement with nothing in the returned value to indicate it. This is what was measured – Nelder–Mead and Gauss–Newton returning 2.39 and 1.52 at one design and reversing at another.

For the evidence, suppose the posterior has modes $k = 1, \dots, K$ contributing $Z = \sum_k Z_k$, and a procedure finds only a subset $\mathcal{S}$. Then

$$\log \hat{Z} - \log Z = \log \left(1 - \sum_{k \notin \mathcal{S}} \frac{Z_k}{Z} \right), \quad (27)$$

so the error is controlled by the *posterior weight* of what was missed. Missing a subdominant mode costs $O(Z_k/Z)$ and missing a negligible one costs nothing. Because the contributions add, a multistart that finds several modes can sum them rather than choose between them, and each additional mode found monotonically improves the estimate. There is no analogue for a minimum, where finding more candidates only ever changes which single one is reported.

This is the whole argument for the change, and it is worth stating plainly: multimodality is a *failure mode* for a minimum and merely a *property of the integrand* for an integral.

Estimating the evidence I: prior sampling, and why it fails here. The direct estimator draws $\theta_s \sim \pi(\theta \mid M)$ and averages the likelihood,

$$\hat{Z} = \frac{1}{S} \sum_{s=1}^S p(Y \mid \theta_s, M, d), \quad w_s = p(Y \mid \theta_s, M, d), \quad (28)$$

which is unbiased for Z , though $\log \hat{Z}$ is biased low by Jensen's inequality. Its reliability rides on the spread of the weights, summarized by the effective sample size

$$S_{\text{eff}} = \frac{(\sum_s w_s)^2}{\sum_s w_s^2} \in [1, S], \quad (29)$$

which equals S when all draws contribute equally and 1 when a single draw dominates. It costs nothing to compute. It is also the only thing standing between this estimator and a confidently reported number with no content.

That it must fail here can be seen in advance. With N samples the log-likelihood scales as $\log p(Y \mid \theta) \simeq -\frac{1}{2} N \bar{d}(\theta)$ for a mean squared discrepancy $\bar{d}$, so weights are $w_s \propto \exp[-\frac{1}{2} N \bar{d}(\theta_s)]$ and the ratio of the two largest is exponential in N . Useful draws are those landing inside the posterior. Its width is $O(N^{-1/2})$ in each of p directions, so the expected number of useful draws is

$$\mathbb{E}[\#\text{useful}] \sim S \cdot \frac{\text{vol}(\text{posterior})}{\text{vol}(\text{prior})} \sim S N^{-p/2}. \quad (30)$$

For the present study $N = 201$, $p = 4$ and $S = 220$, giving $220 \times 201^{-2} \approx 5 \times 10^{-3}$ – fewer than one useful draw.

The measurement agrees exactly. $S_{\text{eff}} = 1.0$ at *every* design tried, with reported values between 793 and 10 979 nats that are pure noise. The standard errors ran 56 to 130 throughout and looked entirely respectable. Without (29) the failure is invisible.

Estimating the evidence II: Laplace. Expand $\log[p(Y \mid \theta)\pi(\theta)]$ to second order about its maximum $\hat{\theta}$ and do the resulting Gaussian integral. As in (5),

$$\log Z \simeq \log p(Y \mid \hat{\theta}) + \log \pi(\hat{\theta}) + \frac{p}{2} \log 2\pi - \frac{1}{2} \log \det H, \quad H = -\nabla^2 \log p(Y \mid \theta) \big|_{\hat{\theta}}. \quad (31)$$

For Gaussian data $H = J^T J + \sum_i r_i \nabla^2 r_i$. Dropping the second term – the Gauss–Newton approximation, valid when residuals are small or the model nearly linear – leaves $H \simeq J^T J$, which the fit already computed. Parameterizing so the prior is uniform on the unit cube makes $\pi(\hat{\theta}) = 1$, and with whitened residuals $r = (m - y)/\sigma$,

$$\log Z \simeq -\frac{1}{2} \|r\|^2 - \frac{N}{2} \log(2\pi\sigma^2) + \frac{p}{2} \log 2\pi - \frac{1}{2} \log \det(J^T J). \quad (32)$$

The first two terms are the best fit; the last two are the Occam factor, and their sign is what prevents a more flexible model from winning on fit alone. Crucially for the present purpose, (32) does not care how sharp the likelihood is, which is precisely the regime that destroyed (28). It is affordable only because the fit uses analytic Jacobians: derivative-free minimization of the same objective costs 55 s against 7.6 s, and the Jacobian needed for $\det(J^T J)$ is a by-product of the solve rather than an extra cost.

The two criteria are consistent where both can be computed. The criteria are not independent, and the relation between them is a check on both. If the true model fits to within noise, $\chi_1^2 \approx N$, while a rival that cannot fit leaves a residual of root-mean-square $T\sigma$, so $\chi_2^2 \approx NT^2$. Substituting into the leading term of (32),

$$\log \text{BF} \approx \frac{1}{2} (\chi_2^2 - \chi_1^2) \approx \frac{N}{2} (T^2 - 1) \xrightarrow{T \gg 1} \frac{N}{2} T^2, \quad (33)$$

up to the Occam terms, which T has no way to express. Testing (33) against the measured values:

design	T (vs SLS)	$\frac{N}{2} T^2$ predicted	measured U (nats)
199 μm , stretch 3.55	0.56	31.5	35.4 ± 12.2
895 μm , stretch 4.93	1.52	232	150 ± 73

Two computations sharing no machinery – one a constrained least-squares minimum, the other a marginal likelihood by Laplace – agreeing to within their stated uncertainty. The residual gap at $895\ \mu\text{m}$ is of the right sign and size for the Occam penalty that qSLS pays for its fourth parameter.

What it costs, and where it is not yet trustworthy. Two prices are paid for removing the minimum, and both are real.

Prior sensitivity. Z depends on $\pi(\theta \mid M)$ through the normalization of (25). Widening a prior by a factor c in each of p directions divides the evidence by roughly c^p without changing the fit at all. This is the Lindley–Jeffreys effect [13, 14], and it is not a defect to engineer away: a model whose prior is diffuse really is less supported by data that pin it down.

But it makes the prior part of the criterion, where T needed none, so the prior must be stated. Centering each rival’s prior on its fit to the *existing* record produced a criterion measuring prior placement instead of discriminability, with every Laplace expansion invalid. The results here use the wide, physically motivated box of the model-selection grid, identical across models on every shared parameter.

Boundary pinning. Equation (31) presumes an interior maximum. In 50–90% of the fits at each design the rival’s best parameters lie on a face of the prior box, where the expansion does not apply and the value is not to be trusted.

That it happens is itself informative. A rival that can imitate qSLS only by driving a parameter to the edge of physical plausibility has, in a meaningful sense, been discriminated against. But saying so needs a criterion built for a constrained maximum, not a quadratic expansion about an interior one. Which parameter pins, and whether the pinning is physical or an artifact of the box, is the outstanding step.

The honest summary: the integral criterion is better founded than T and not yet more reliable on this problem. The multimodality that made T untrustworthy is genuinely gone. What replaces it is a dependence on the prior – now explicit rather than hidden – and a boundary condition the current estimator does not handle.

Which criterion the conflict is between

The scaling argument of Section 3.7 says a design change that merely amplifies signal leaves the condition number κ untouched. Degeneracy is a property of the eigenvectors, and only a design that rotates them can remove it.

For these records, E-optimality preferred a larger bubble ($895\ \mu\text{m}$, $\lambda_{\min} = 12.8$). Conditioning and eigenvector composition preferred a gentler collapse at the present size ($277\ \mu\text{m}$ at stretch 5, $\kappa = 4.2 \times 10^3$, the modulus–stiffening share of the worst direction falling from 87% to 66%). Both are correct answers to different questions, and (15) says which one matters here.

So there are two distinct disagreements in play, and they have different resolutions. The classical criteria disagree among themselves because they summarize one spectrum differently; that is a choice about what one wants to learn. Estimation and discrimination disagree because they are about different quantities altogether. The next subsection resolves the second, and in doing so dissolves the first.

Designing over measures, and certifying the answer

Every design result above shares a defect that no amount of care in computing them repairs: each is the output of a search over a single design point, that search is not convex, and nothing in its output distinguishes a good answer from a bad one. The evidence that this is not hypothetical is in the preceding subsections. A surrogate search recovered 16% of the best conditioning actually available and reported the result without qualification; a dense grid over a criterion whose inner minimization was unreliable produced a front that was precise and wrong. Both look exactly like success.

The classical formulation removes the defect rather than mitigating it.

Designs as measures. Instead of choosing one design x from a candidate set $\mathcal{X}$, choose a probability measure ξ on $\mathcal{X}$: run a fraction ξ_i of the bubbles at setting x_i . This is not an abstraction imposed for mathematical convenience – it is what an experimenter with a run budget does anyway, and it is strictly more expressive,




Figure 17: The certificate, which is what makes an optimal design a proof rather than a stopping rule. Kiefer and Wolfowitz: a measure ξ^* is D -optimal *if and only if* its sensitivity $d(x, \xi^*)$ never exceeds the parameter count p anywhere in the design space, and attains p exactly on the points carrying weight. Both halves are visible at once – a curve capped by a level it touches and never crosses – so a search reports not merely that it stopped improving but that there is nowhere left for a better design to hide. The gap $\max_x d(x, \xi^*) - p$ is the proof’s residue; 10^{-9} in the designs here.




Figure 18: A design is a measure, not a point. Each candidate x_i carries an information matrix $M(x_i)$, and a design assigns weights ξ_i summing to one, read as the fraction of runs spent at that candidate. The averaged information $M(\xi)$ is linear in ξ , so any concave function of it is concave in the design, and the maximization becomes convex. That convexity is what makes Figure 17 possible: a local optimum is global, and a certificate can therefore exist. Weights of zero are the common case, so the support of the optimal measure is usually a handful of designs out of hundreds.

since a single design is the special case of a measure concentrated on one point. The information available from a run allocated by ξ is the average

$$M(\xi) = \sum_i \xi_i M(x_i), \quad M(x) = J(x)^\top J(x), \quad (34)$$

because information from independent runs adds and ξ says how many of each to take.

The consequence is the whole point: $M(\xi)$ is *linear* in ξ .

Concavity, and why the first-order condition is enough. $\log \det$ is concave on the positive-definite cone, and the composition of a concave function with a linear map is concave, so $\Phi(\xi) = \log \det M(\xi)$ is concave on the simplex – a convex set. A concave function on a convex set has no local maximum that is not global, and its first-order condition is not merely necessary but sufficient. Every pathology this study ran into – wrong basins, surrogate blind spots, answers that improve whenever the optimizer does – is a symptom of non-convexity, and none of them can occur here.

The same holds for $\Phi_A = -\text{tr} M(\xi)^{-1}$ and $\Phi_E = \lambda_{\min}(M(\xi))$, and for any non-negative combination of concave criteria.

The directional derivative. Move mass α from ξ toward the single design x , giving $\xi_\alpha = (1 - \alpha)\xi + \alpha \delta_x$. By linearity $M(\xi_\alpha) = (1 - \alpha)M(\xi) + \alpha M(x)$, and using $\partial \log \det A = \text{tr}(A^{-1} \partial A)$,

$$\phi(x, \xi) \equiv \left. \frac{\partial}{\partial \alpha} \log \det M(\xi_\alpha) \right|_{\alpha=0} = \text{tr}[M(\xi)^{-1} M(x)] - p. \quad (35)$$

For a linear utility u averaging over the design, the same construction gives $\phi_u(x, \xi) = u_x - u^\top \xi$.




Figure 19: How the optimal design is found. Every candidate starts with equal weight, and each step multiplies a candidate’s weight by how informative it is relative to the current average, then renormalizes. Weights therefore stay positive and keep summing to one by construction, and the criterion increases at every step. Candidates that are not worth running decay to zero, so the answer is a handful of settings out of hundreds. The final weights are the fraction of bubbles to run at each setting, and Figure 17 is what certifies that no other allocation does better.

The General Equivalence Theorem. Since Φ is concave and the simplex is the convex hull of its vertices δ_x , the measure ξ^* maximizes Φ if and only if no vertex direction ascends:

$$\boxed{\xi^* \text{ is D-optimal} \iff d(x, \xi^*) \equiv \text{tr}[M(\xi^*)^{-1}M(x)] \leq p \text{ for all } x \in \mathcal{X},} \quad (36)$$

with equality at every support point of ξ^* . This is the theorem of Kiefer and Wolfowitz [3], and it is what this section exists to obtain: a quantity computed from a candidate answer that *proves* the answer optimal. The gap $\max_x d(x, \xi) - p$ is a certificate, not a convergence report.

Two further facts come free. Equality puts the support exactly where $d(x, \xi^*)$ is largest, so the optimal design runs at the settings of greatest standardized prediction variance. D-optimality and G-optimality coincide. And by Carathéodory’s theorem applied to the convex hull of the $M(x)$, an optimal measure supported on at most $p(p+1)/2 + 1$ points always exists: at most 11 here.

Computing it. The implementation uses the multiplicative algorithm of Silvey, Titterton and Torsney [15],

$$\xi_i \leftarrow \frac{\xi_i F_i}{\sum_j \xi_j F_j}, \quad F_i = \text{tr}[M(\xi)^{-1}M(x_i)] \text{ for } \Phi = \log \det, \quad (37)$$

which stays on the simplex by construction: weights remain non-negative and normalized without projection, and the criterion rises at each step. Note that $\sum_i \xi_i F_i = p$ identically, so (37) moves mass toward designs whose $d(x, \xi)$ exceeds p , which is precisely the set that (36) says must be empty at the optimum. The update and the certificate are the same quantity.

Vertex-direction steps with a line search were tried first and cannot converge here. The step required near the optimum falls below any fixed search grid, and the iteration stalls with a positive gap.

Convergence of (37) degrades as candidates crowd together. A design just off the support is nearly as good as one on it, and its weight decays in proportion. Certifying a parabola on $[-1, 1]$ took 6400 iterations over 51 candidates, 25 000 over 101, and 329 000 over 401 – with the criterion value correct to six figures long before any of those.

An exhausted budget therefore yields a converged value without a proof. That is a different thing from a wrong answer, and the reported gap distinguishes them.

The certified design for these records. Over 480 candidates spanning $R_{\max} \in [50, 1200] \mu\text{m}$ and stretch $[3, 20]$, with $M(x) = J^\top J$ for the four qSLS parameters at the posterior median, the algorithm certifies at a gap of 9×10^{-10} in 1406 iterations: $\max_x \text{tr}[M^{-1}M(x)] = 4.00000000$ against $p = 4$. The optimal measure is

$R_{\max}$	stretch	weight
1015 μm	6.70	0.470
161 μm	19.26	0.303
50 μm	17.78	0.227

against a best single design of 1015 μm at stretch 6.70. The measure exceeds it by 6.99 in log det, a D-efficiency ratio of $\exp(6.99/4) = 5.74$; equivalently the confidence ellipsoid is $\exp(6.99/2) \approx 33$ times smaller in volume, and a typical parameter’s interval is $\exp(6.99/8) = 2.4$ times tighter. No single design can match it, and this is not a claim about the search: (36) certifies that none exists.




Figure 20: The equivalence-theorem certificate. Left: the sensitivity $d(x, \xi^*) = \text{tr}[M(\xi^*)^{-1}M(x)]$ over the design plane, with the three support points circled and labeled by weight; the dashed contour is the level $p = 4$. Right: the same values sorted. No design exceeds the bound and the support attains it exactly, which is the proof – $\max_x d = 4.00000000$ against $p = 4$, gap 9×10^{-10} . Nothing analogous exists for the single-design searches elsewhere in this document.

The mixture is the resolution of the conflict. The support is worth reading physically. Nearly half the runs go to a large, gently driven bubble and the rest to small, hard-driven ones – the two corners the earlier subsections found pulling in opposite directions. Separating g from α wants a gentle collapse, because the distinguishing term of Z_e decays as λ^{-4} ; exciting the relaxation mode wants a fast one.

A single design must choose between them. A measure need not. So the trade-off that motivated the Pareto front dissolves once the design space is the one the experiment actually admits – the front was answering a question made hard by an artificial restriction.

Discrimination in the same frame. Log evidence is additive over independent experiments, so an expected log Bayes factor per run is linear in ξ and therefore concave. The compound criterion

$$\Phi_\beta(\xi) = (1 - \beta) \log \det M(\xi) + \beta u^\top \xi, \quad \beta \in [0, 1], \quad (38)$$

is then concave for every β and inherits the certificate unchanged. Its directional derivative is the matching combination of (35) and $u_x - u^\top \xi$. This is the compound-criterion construction of Atkinson and of Cook and Wong [16, 17] – the principled form of the trade this study otherwise handled by search.

Sweeping β traces the Pareto front, and each criterion being concave in ξ makes that front convex. This is why the classical literature scalarizes with weighted sums where this study needed a Chebyshev form. The non-convexity that forced the elaborate scalarization was an artifact of optimizing over a single design point.

Temperature is the only axis on the table that rotates rather than amplifies. Section 3.7 proves that a design change which merely amplifies signal sends $F \rightarrow sF$, leaving κ untouched, so degeneracy can only be removed by a design that rotates the eigenvectors. Every candidate in this chapter is $(R_{\max}, \text{stretch})$, and both are drive settings. Temperature is not: it moves the material’s own $g\alpha$, it costs nothing but a bath, and it has never been a design variable here.

The obstruction is that each temperature has its own parameters, so three records at three temperatures are three separate fits with nothing to design *for*. Temperature becomes an axis only under a model that shares parameters across it, and the weakest such model that is still physics is Arrhenius, $\log \theta_a(T) = c_a + b_a(1/T - 1/T_{\text{ref}})$: two coefficients per axis, six in all, with the chain rule turning a trace’s sensitivity to $\log \theta_a$ into sensitivities to (c_a, b_a) , the second scaled by $(1/T - 1/T_{\text{ref}})$.




Figure 21: Why a model difference can be invisible at every design. Changing a model perturbs the trace by $\Delta = R_B - R_A$. The component lying in the span of the material sensitivities is reproduced by adjusting $g, \mu, \lambda_1, \alpha$ – refitting absorbs it, and no experiment recovers it. Only the orthogonal remainder is evidence that the model changed. Measured on the 15 °C record and reported in Section 7: the bubble-dynamics operator is 77.7% absorbed, leaving under two noise units, which is why its ranking proved so fragile; the constitutive and thermal axes leave 8.1 and 8.5.

Under that model the comparison is not close, and not subtle. *With temperature held, the six-parameter information is singular and the design is refused.* That is near-tautological once stated — a slope cannot be measured at one point, so the b_a columns are exact multiples of the c_a columns and the rank is three, not six — and it is exactly the abstract claim of Section 3.7 made concrete: no optimization over geometry, at any budget, identifies the temperature dependence. Only varying temperature does. Freeing it certifies at a gap of 8×10^{-10} on six settings spanning 12 °C to 36 °C, with $\log \det = 5.15$ and $\kappa = 2.8 \times 10^9$ where the held design has no finite κ at all.

This is the most conditional result in the chapter and is reported as such. Three temperatures fitting six coefficients leaves one residual degree of freedom per axis, so the Arrhenius form is assumed rather than tested; its residuals, ± 0.005 in $\log \mu$, ± 0.05 in $\log g\alpha$ and ± 0.13 in $\log \lambda_1$, are a consistency note and nothing more.

What this does not fix. Three limitations, stated plainly. The information matrices are evaluated at a point estimate of θ , so the design is locally optimal in the parameters though globally optimal in ξ . A prior average over θ restores the guarantee at proportionate cost, since the average of concave criteria is concave.

The candidate set is still a grid, so the certificate proves optimality *over that grid*. But $d(x, \xi^*)$ can be evaluated anywhere, which makes checking for a missed region a cheap scan rather than another search.

The compound form was not run on these records. The per-design log Bayes factor still suffers the boundary pinning described above.

12 One criterion, and what a budget buys

Section 13 gives a recipe and Section 3.7 shows the criteria in it disagree. Both leave a question unanswered: the material is scored by $\log \det M$, the model label by a Schur complement, the initial radius by a separate study, and none of the three share a scale, so *which* question a batch should serve cannot be asked. They are one quantity.

The value of an experiment

What an experiment is worth is how much it moves your beliefs, and about *what* is an argument rather than a fixed choice. Write A for the quantity of interest — parameters, a model label, the initial radius, the noise scale, any subset — and the value of a design is the mutual information between the data and A ,

$$U_A(\xi) = \mathbb{E}_y[\text{KL}(p(A | y, \xi) \| p(A))] = I(A; Y | \xi). \quad (39)$$

For a Gaussian likelihood in prior-standardized coordinates — the unit-cube scaling Section 3.4 already uses, in which the prior covariance is the identity — the posterior precision is $N = I + M(\xi)$ and (39) is available in closed form. Partitioning into the coordinates A and the nuisance coordinates B ,

$$U_A(\xi) = \frac{1}{2} \log \det \left[N_{AA} - N_{AB} N_{BB}^{-1} N_{BA} \right], \quad (40)$$

the Schur complement of everything you are not asking about. Every criterion in this document is (40) at a different A : all coordinates gives Bayesian D-optimality, the material block gives Section 3.7's log det, the mixing coordinates of Section 13 give D_s -optimality, and `req.scale` alone asks whether the initial radius is driving the conclusion. Answers in nats are comparable across those, and with weights π_A they add, $\Phi(\xi) = \sum_A \pi_A U_A(\xi)$.

The choice that was hiding in log det M

That the criteria are one family also exposes a decision nobody made. For any partition,

$$\log \det M = \log \det M_{\theta\theta} + \log \det S, \quad S = M_{\varepsilon\varepsilon} - M_{\varepsilon\theta} M_{\theta\theta}^{-1} M_{\theta\varepsilon}, \quad (41)$$

so maximizing log det M over the augmented set, as Section 13 does, is maximizing material log-volume *plus* discrimination log-volume with equal weight. That is a defensible compromise and it is not neutral, which is what it had been taken to be.

Three properties, and one that removes a failure

(40) is concave in ξ for every A . The Schur complement has the variational form $u^\top S u = \min_v (v, u)^\top N (v, u)$, a pointwise minimum of functions linear in N , hence matrix-concave; log det is concave and matrix-monotone, so the composition is concave, and $M(\xi)$ is linear in ξ . The equivalence theorem of Section 11 therefore still applies. With $P = \begin{pmatrix} I_A \\ -N_{BB}^{-1} N_{BA} \end{pmatrix}$ the envelope theorem gives the directional derivative, and ξ^* is optimal exactly when

$$d(x, \xi^*) = \frac{1}{2} \text{tr} [S^{-1} P^\top M(x) P] \leq \frac{1}{2} (|A| - \text{tr} [S^{-1} P^\top P]) \quad \text{for all } x, \quad (42)$$

with equality on the support. The bound is computed rather than looked up — it is p for log det and depends on ξ here — but it is still a proof and not a convergence report.

The prior term I in N is what makes (40) finite when M is singular. Under log det M a design that cannot determine every parameter scores $-\infty$ and cannot be ranked at all, which is how 22 of 48 candidate geometries became unscorable in Section 11. Here such a design scores low, which is the truth about it.

One caution follows from (41) being nonlinear: S is not linear in M , so $\log \det S(\sum_i \xi_i M_i) \neq \sum_i \xi_i \log \det S(M_i)$. Scoring candidates one at a time and taking the best N is therefore wrong — a design that discriminates well alone but leaves θ loose has its advantage eaten when the material is refitted from the same batch, and only the Schur complement of the *summed* information sees that.

Will it settle? A budget in bubbles

Nats say how much a batch teaches. They do not say whether it decides anything, which is what a collaborator with a fixed budget is asking. That has a closed form, and it is exact in the Gaussian-linear limit rather than asymptotic.

Let s be the per-run information about the coordinate separating two models, after everything else is fitted out. Information adds over independent runs, so N runs give $S = Ns$. Writing d for the component of the whitened model difference orthogonal to the material span, so that $S = \|d\|^2$ as in Figure 21, data generated under one model give a profiled log Bayes factor

$$\Lambda = \frac{1}{2} (\|d + n_\perp\|^2 - \|n_\perp\|^2) = \frac{S}{2} + d \cdot n_\perp, \quad \text{so} \quad \Lambda \sim \mathcal{N}\left(\frac{S}{2}, S\right), \quad (43)$$

since $d \cdot n_\perp$ has variance $\|d\|^2 = S$. The experiment has not been run and its Bayes factor is unknown, but its *distribution* is known before anyone books the laser. The chance of clearing δ nats in favour of the truth is $\Phi((S/2 - \delta)/\sqrt{S})$, and inverting for confidence $1 - \alpha$ gives the budget

$$N \geq \frac{(z_{1-\alpha} + \sqrt{z_{1-\alpha}^2 + 2\delta})^2}{s}. \quad (44)$$

At $\delta = 5$ nats and 95% confidence the numerator is 27.14. An s of zero — the difference wholly absorbed, the infinite variance of Section 7 — sends (44) to infinity, which is the statement that no experiment of this shape ever settles the question.

The same unit serves the parameter question. After N runs the posterior standard deviation of coordinate k is $[(I + NM)^{-1}]_{kk}^{1/2}$ in prior-standardized coordinates, so “pin g to a tenth of its prior width” is also a number of bubbles. That shared denominator is what makes the two comparable; nats alone are not, because they measure different things about different objects.

What the criterion cannot reach

Every A above is a *coordinate*. “Is every model in the catalogue wrong?” is not one, and Section 5.2 answers it *yes* on all three records. No column of the Jacobian reaches model inadequacy, and worse, (39) maximized freely walks away from the batch that could detect it: a criterion linear in ξ is optimized by a single setting repeated N times, which has no pure error and no lack-of-fit numerator.

Testability is therefore a *constraint* on the batch, not a term in the objective:

$$\max_{\xi} \sum_A \pi_A U_A(\xi) \quad \text{subject to} \quad |\text{supp } \xi| \geq k > p, \quad n_i \geq J \geq 2. \quad (45)$$

The replication half is cheap and does nothing here: the number of settings is a property of the *measure*, and apportionment only allocates runs within the support it is handed, so forcing three replicates on the operator design leaves the batch at two settings and $\text{df} = -2$ still.

The support half is a cardinality constraint and is not convex, so it cannot join the objective without forfeiting (42). `pyimr.measure.constrained_measure` buys most of the certificate back in two steps. Which settings to guarantee — the set $\mathcal{K}$, of size k — is decided by the certificate itself: those the free solution already funds, then the candidates of largest sensitivity, the ones (36) shows the free problem came closest to wanting. Naming them is not enough, since an optimizer merely restricted to a larger candidate set reproduces the free optimum by leaving the new settings at zero and reports no cost at all; they are guaranteed instead by the substitution

$$\xi = c \mathbf{1}_{\mathcal{K}} + (1 - kc) \eta, \quad c > 0, \quad kc < 1, \quad (46)$$

which maps $\{\xi : \xi_i \geq c \ \forall i \in \mathcal{K}\}$ onto the whole simplex in η . The search is then exactly the one (42) already certifies, the floor holds by construction rather than by projection, and every candidate — guaranteed or not — still competes for the remaining mass $1 - kc$. What is certified is optimality *among measures meeting the floor*, which is weaker than (42) and is reported as such.

On the operator design the constraint is worth paying. The free batch takes two settings for 4.39 nats; held to five it spreads over six geometries and $\text{df} = +2$ for 0.10 nats, and held to seven it reaches $\text{df} = +3$ for 0.04 — both certified below 10^{-9} . That seven costs less than five is not a paradox: the default floor is half an equal share, so asking for more settings also asks less of each, and the two demands are not nested. At a fixed c they are, and the price rises with k as it must.

The answer for these records

Over the 227 candidate geometries of Section 13 at a budget of twelve, with the material held at the 15 °C fit:

batch optimized for	material (nats)	operator (nats)	settings	lack-of-fit df
material	19.51	3.78	7	+3
operator	17.03	4.39	2	−2
portfolio, 1:4	18.92	4.24	6	+2

all three certified at gaps below 10^{-9} . The geometry does move with the question — the operator question wants 785 μm at stretch 6.9, which the material-optimal batch never visits — but the portfolio buys 97% of each for 3%, and is the only aggressive option that stays testable *at this noise model*.

That qualification is not decoration. Every number in the table takes $\sigma = 0.018 R_{\max}$ at every sample, and Section 15 shows the records contradict it by two to three orders of magnitude within a single trace.

Recomputed under the measured profiles the portfolio’s six settings become four and its df becomes zero on two of the three, so the last clause of the paragraph above holds only under the flat scale that motivated it. The repair costs two tenths of a percent and is given there, along with the batch this document actually recommends.

A note on the search. The multiplicative algorithm of Section 11 relies on $\text{tr}[GM(\xi)]$ being the constant p , which holds for log det and for nothing else; on the operator design it stalls at a gap of 0.155. It reports itself uncertified, which is the certificate working, but mirror descent on the simplex is what converges here, to 1.8×10^{-10} and a higher value.

What all of this is worth against correlated noise

Every number above is information, and Section 5.3 shows this likelihood counts more of it than it has. The correction belongs here rather than as a caveat, because it enters (44) directly: s falls, and the required budget rises by the same factor.

Replacing independent samples with the exponential covariance $\Sigma_{ij} = \sigma_i \sigma_j e^{-|t_i - t_j|/\tau}$ makes the whitened information $J^T \Sigma^{-1} J$, and everything above inherits it unchanged — the criterion, the certificate and (44) are all statements about M , whatever M was computed from. The effect is not a single deflation. Measured at $\rho = 0.908$: a constant offset loses a factor of 0.053, a smooth half-cycle 0.049, a five-cycle oscillation 0.176, while point-to-point jitter is *amplified* 20.7-fold. Model differences are smooth, so the deflation is what applies to every margin in this document, but it is a fact about the shape of those differences rather than a property of the likelihood.

Applied rather than quoted, it changes neither the design nor, here, its sign. The paragraph above is a statement about idealized shapes. Recomputing every geometry with $M = J^T \Sigma^{-1} J$ at $\tau/t_c = 0.292$ — the correlation length transferred by phase, for the reason Section 15 gives for σ and under Section 11’s caveat — settles what it does to the answer, and the answer is two negatives and one positive.

The recommended geometry does not move, under any of the three measured noise profiles: the diagonal and correlated likelihoods pick the same design in all three cases. So the batches of this chapter are not misdirected by the likelihood they were computed under, which is the more important of the two questions and the one the deflation figures leave open.

Nor is the operator question deflated. The discrimination coordinate is *amplified*, by a median of $\times 3.23$, $\times 2.85$ and $\times 2.51$ across the three profiles, over a range running from $\times 0.52$ to $\times 10.4$. There is no contradiction with the figures above: those are the deflations of a constant offset and a smooth half-cycle, and the operator differences on this grid are not smooth enough to sit there.

The mechanism, however, is exactly the one the figures imply, and that is the positive result. Ranked against the fraction of each difference’s energy above eight cycles across the record, the amplification correlates at +0.66, +0.64 and +0.65. A correlated likelihood pays for a difference that is *fast* and charges for one that is smooth, so which feature of a design is worth buying does change even where the ranking does not.

13 Choosing the next N experiments

Everything above scores designs. None of it answers the question a collaborator actually asks: *we can run N more bubbles, what should they be?* This section is that recipe. It is five steps, four of which are already derived above and one of which is new.

Step 0: ask which questions are still open

A batch that separates models the records have already separated buys nothing. Given the log evidence $\log Z_m$ of each rival on the data in hand, write the margin against the best, $\Delta_m = \log Z_m - \max_k \log Z_k$, and call a rival *decided* when $\Delta_m < -\delta$ for a threshold δ we take as five nats. Survivors carry the posterior they have earned,

$$w_m = \frac{e^{\Delta_m}}{\sum_{k \text{ live}} e^{\Delta_k}}, \quad w_m = 0 \text{ for decided } m. \quad (47)$$

This step does more than save runs. The criterion below is *local* — it linearizes the model difference — which is the right approximation for rivals that are close and the wrong one for rivals far apart. But rivals far apart are easy to separate and are exactly the ones (47) decides. What survives screening is the close pairs, which is the regime the linearization is valid in, so the two failure modes cancel rather than compound.

Step 1: make the model choice a parameter

For a live rival m against the incumbent, write $R(\theta, \varepsilon_m) = (1 - \varepsilon_m)R_{\text{inc}}(\theta) + \varepsilon_m R_m(\theta)$, so that $\partial R / \partial \varepsilon_m = R_m - R_{\text{inc}}$ at $\varepsilon_m = 0$. The model question becomes one more column of the Jacobian. With the material sensitivities whitened by the measurement deviation, the augmented Jacobian at a candidate setting x is

$$\tilde{J}(x) = \left[\underbrace{\sigma^{-1} \partial R / \partial \theta}_{p \text{ columns}} \mid \underbrace{\sqrt{w_1} \sigma^{-1} \Delta_1 \cdots \sqrt{w_q} \sigma^{-1} \Delta_q}_{q \text{ rivals}} \right], \quad M(x) = \tilde{J}(x)^\top \tilde{J}(x). \quad (48)$$

The $\sqrt{w_m}$ is what makes (47) bite: a rival at a tenth of the posterior contributes a tenth of the information about its own coordinate, and a decided rival contributes none.

Nothing is sampled here. This is the point at which an expected log Bayes factor would normally be estimated, and Section 11 explains why that estimator fails on records this long — the effective sample size collapses to one. The derivative is exact, costs one Jacobian, and needs no prior on the rival, which also removes the prior-placement trap of Section 11: only the difference direction enters, never the rival’s own parameters.

Step 2: optimize over measures, not over settings

A batch is a measure. Let ξ put weight ξ_i on candidate x_i ; the information is $M(\xi) = \sum_i \xi_i M(x_i)$, *linear* in ξ , so $\log \det M(\xi)$ is concave and

$$\xi^* = \arg \max_{\xi} \log \det M(\xi) \quad (49)$$

has no local optima. Because M carries both blocks, (49) balances estimating the material against determining which model produced the trace without any weighting parameter to choose.

This is deliberately not the compound criterion of Section 11. That form blends $\log \det$ with a utility, and the blend is concave only because the utility is *linear* in ξ . The natural discrimination utility — the posterior variance of ε — is not linear, so blending it would forfeit the certificate. Putting ε inside the matrix keeps one concave criterion and the proof that comes with it.

Step 3: certify

By Kiefer–Wolfowitz, ξ^* solves (49) exactly when no candidate setting offers an uphill direction:

$$d(x, \xi^*) = \text{tr}[M(\xi^*)^{-1} M(x)] \leq p + q \quad \text{for all } x, \quad (50)$$

with equality on the support. The gap $\max_x d(x, \xi^*) - (p + q)$ is a proof, not a convergence report, and it is what distinguishes this from every single-design search in this document.

Step 4: spend the budget

ξ^* is a measure and the experiment runs integers. For a budget of N , apportion by efficient rounding [18]: give every support point one run and allocate the rest by the rule that maximizes $\min_i n_i / (N \xi_i^*)$, so no support point is rounded away. The rule carries no guarantee at small N , which is the regime here, so the loss is *measured* rather than assumed:

$$\text{D-efficiency} = \left(\frac{\det M(n/N)}{\det M(\xi^*)} \right)^{1/(p+q)}. \quad (51)$$

What the batch buys is then read off the inverse. The variance of the coordinate that says which model produced the trace, after the material has absorbed everything it can, is the Schur complement

$$\text{Var}(\varepsilon_m) = \left[(M_{\varepsilon\varepsilon} - M_{\varepsilon\theta} M_{\theta\theta}^{-1} M_{\theta\varepsilon})^{-1} \right]_{mm}, \quad (52)$$

and an infinite entry is the statement that no design separates that pair at all — the difference lies entirely in the span of $\partial R/\partial\theta$ and refitting reproduces it.

The answer for these records

Screening (47) on the operator axis leaves five live rivals against Gilmore/Mie–Grüneisen. Over 48 candidate geometries spanning 50 μm to 1200 μm and stretch 3 to 20, (49) certifies at a gap of 10^{-9} on five support points, and a budget of $N = 12$ apportions to

R_{max}	stretch	runs
1200 μm	9.8	6
1200 μm	6.4	3
307 μm	16.6	1
50 μm	20.0	1
484 μm	6.4	1

at 99.6% of the measure’s own efficiency. Against spending all twelve at the geometry already performed, (52) falls by 16.0, 17.7 and 9.3 times for Gilmore/Tait, Keller enthalpy/Tait and Keller enthalpy/Mie–Grüneisen respectively.

Two caveats travel with that table. Every design that integrates is scorable here, where the sampled criterion could rank only 26 of the same 48 — but the criterion is still evaluated at one material and one incumbent, so it is locally optimal in exactly the sense Section 15 shows can mislead under model error. And the screening that produced the rival list rests on margins computed under an independent likelihood; Section 14 shows that deflating them by N/N_{eff} changes which rivals are live at all.

Staging the budget buys nothing, and why that is worth reporting

Everything above commits all twelve runs before any is taken, which is the wrong default when Section 14 says the rival list itself is uncertain. Equation (43) prices the alternative without any new machinery: the log Bayes factor of a stage of N_1 runs is $\mathcal{N}(N_1 s_m/2, N_1 s_m)$ before anyone books the laser, so the batch can be simulated, re-screened at the same five nats, re-certified for the survivors, and finished.

Swept over budgets of 2 to 12 and every split of each, the gain is +0.000 rivals at every split. The reason is visible one column left: the one-shot arm already decides all four live operator rivals at a budget of *two*, at 971 μm and stretch 5.62. There is nothing for a second stage to reallocate.

That is a statement about the geometry rather than about staging, and it is the useful part. The operator margins this document reports from the records are small — under a nat at 23 and 33 °C once R_{eq} floats (Section 8) — because the records sit at 277 μm and stretch 7.09, not because the question is hard. At a geometry chosen for it, one bubble settles it.

Two things had to be fixed before this number meant anything, and both are worth naming because both looked like results. Run without Step 0, the rival list includes Rayleigh–Plesset, whose separation from the compressible operators spans eleven decades and saturates every budget — compressibility is not in doubt, by 74 to 182 nats, and screening is what removes it. And the constitutive axis has no live rival at 15 °C at all: SLS trails by 1496 nats, or 74 deflated, so a test that appeared to run on it was matching SLS as a substring of qSLS and scoring the incumbent against itself.

14 Which questions are open

Step 0 of Section 13 asks which rivals the records have already decided. Run on this package’s three axes, the answer is stark and then immediately contingent.

At face value almost nothing is still in question. Of seventeen constitutive candidates, one is live on every record; the rest trail by up to 4573 nats. Of the six operators scored, two survive on every record. Each record admits a single thermal treatment.

That reading would mean the design of Section 13 is aimed at a question already settled, and by a wide margin. It does not survive the likelihood.

Every log evidence in this document assumes the residuals are independent, and Section 17.1 measures N_{eff} near 10 of 201. Evidence differences scale with the count of independent observations, so each margin is inflated by roughly N/N_{eff} . Deflating by that factor and re-screening:

axis	live at face value	live deflated by N/N_{eff}
constitutive (17 candidates)	1	2
bubble dynamics (6 operators)	2–5	5–6
thermal treatment (3)	1	3

SLS returns, five or six operators return, and every thermal treatment returns.

Screening is where this matters most, and the reason is structural rather than numerical. Elsewhere the correlation inflates a quantity we report and compare — an evidence, a χ^2/N — and the ranking survives because every model is inflated alike. Section 17.1 says exactly that: the ranking survives, the absolute claim does not. But a screen converts a margin into a *yes or no*, and a twentyfold factor moves margins across a threshold wholesale. Here the inflation does not cancel, because the comparison is no longer between models but between a margin and a constant.

So which model questions are open is at present undetermined — and undetermined by the likelihood rather than by anything about the models.

But the design need not wait for it. The reading above makes the correlated likelihood a precondition for the design work, and it is not one. What is fragile is the *threshold*, not the deflation: elsewhere every model is inflated alike and the ranking survives, while (47) compares a margin to a constant, and a factor of twenty moves margins across a constant wholesale.

Section 15 met this shape of problem once already and its finding is the recipe — averaging over a family gave the worst worst case of the five batches compared, and maximizing against the hardest member won on every count. Here the family is the one-parameter deflation $N/N_{\text{eff}} \in [1, 25]$ and the hardest member is the largest, since it revives the most rivals. Scoring each batch by the share of the genuinely live questions it funds, under both readings of the truth:

axis	batch designed at face value	batch designed at full deflation
constitutive	0.978	1.000
bubble dynamics	0.595	1.000
thermal treatment	0.410	1.000

worst case over the two truths. The maximin batch has none: it funds every live question whichever reading is right. The face-value batch funds two fifths of the thermal questions if the deflation is real.

The asymmetry is why, and it is not an artifact of the scoring. A batch designed at full deflation and met by a face-value truth spends 0.595 of its effort on rivals that were already decided — wasted, and recoverable by simply not believing the answer about them. A batch designed at face value and met by a deflated truth never asks about the rivals it wrote off, and no amount of later analysis recovers a question that was never funded. Wasted effort and an unasked question are not symmetric costs, and the maximin choice is the one that trades the first for the second.

15 What the design survives

The certified measure of Section 11 is a theorem. Three things stand between it and an experiment somebody can run, and each is measurable rather than arguable.

A measure assigns weights; an experiment runs integers

The optimum splits runs three ways. With twelve bubbles that is 5.4/3.7/2.9, and the equivalence theorem certifies optimality over *measures* — an exact design is not one, so the certificate does not reach it. `pyimr.measure.apportion` closes the gap by the efficient rounding of Pukelsheim and Rieder, and because that rule carries no guarantee at small budgets, it reports the D-efficiency it achieved rather than asserting one.

On the four-point design of cubic regression, where every quantity is closed form: budgets divisible by four lose nothing, and six runs give 2/2/1/1 at an efficiency of 0.9428, which is $[(2/6)^2(1/6)^2/(1/4)^4]^{1/4}$ exactly. The rule earns its complexity on awkward budgets — at weights 0.7/0.2/0.1 and four runs, proportional rounding gives 3/1/0, dropping a support point and leaving the information matrix singular.

Frames are a design variable, and there are far too many of them

Section 17.1 reports 201 samples carrying the information of about ten. Redundancy is a design variable: a camera trades frame rate against window length, against exposure, and against how many bubbles fit in a session. Scoring frames by $\log \det J^T J$ at the fitted qSLS, with the same number of observations spent each way:

observations	uniform	optimally placed	gain
201	18.54	25.72	6.0×
50	11.73	20.15	8.2×
12	5.98	14.42	8.3×

The D-optimal measure over the 201 candidate times is certified at a gap of 10^{-10} on *six* support points. Fifty observations placed on those six carry more information than all 201 spread uniformly.

That is a measurement of slack, not a recommendation. A design on six distinct times leaves no degrees of freedom to notice the model is wrong, and the lack-of-fit test above is exactly what those degrees of freedom buy. The honest reading is that frames are cheap relative to their information, so the camera should be traded for something scarce — bubbles, or window, or the replication that makes (16) possible.

Bubbles against frames, priced

That trade can now be made quantitative, because Section 5.3 measures Σ . Every batch in this document is chosen over *geometries*, with the number of trials J and the samples per trial N fixed at whatever the records happened to use. Under independent noise that omission is harmless — information is proportional to JN and only the product matters. Under trial-to-trial variation it is not, and the asymmetry is exact. Averaging J trials of an N -sample trace and applying the Woodbury identity to (17),

$$F(J, N) = J(\Sigma + F_N^{-1})^{-1}, \quad F_N = G^T \Sigma_\epsilon(N)^{-1} G, \quad (53)$$

with F_N the information a single N -sample trace supplies. Trials enter linearly and never saturate. Samples enter only through F_N , and as $N \rightarrow \infty$ the bracket tends to Σ , so $F \rightarrow J\Sigma^{-1}$ and further frames buy *nothing*. Past a point, more samples measure one bubble ever more precisely rather than the population.

At a fixed frame budget $S = JN$ this bites: $F = (S/N)(\Sigma + F_N^{-1})^{-1}$, and once F_N^{-1} is small against Σ the prefactor S/N is all that survives, and it *falls* with N . Measured on the records, at each one's own total:

record	as run	best split at the same frames	gain
15 °C	$J = 18, N = 201$	$J = 72, N = 50$	+3.93 nats
23 °C	$J = 14, N = 192$	$J = 56, N = 48$	+3.96 nats
33 °C	$J = 7, N = 198$	$J = 28, N = 49$	+3.40 nats

Doubling the samples buys 0.035 to 0.188 nats. Four times the bubbles at a quarter the frames each, for the same total, buys three and a half to four.

That number should be read against every other design effect in this document. Choosing the geometry under the wrong noise model costs at most 1.34 nats (Section 15); restoring testability costs 0.01 to 0.24; the spread across robust and per-record batches is 0.21. **The allocation nobody has been optimizing is worth three to ten times any of them**, and it is the one variable the batch optimization of Section 13 has never been allowed to move.

Three caveats, and they do not cancel. The trials column of (53) gains exactly $p \log 2$ per doubling because F is linear in J — that is arithmetic, and the measurement is the sample column beside it. F_N is scaled

linearly in N here, as though samples within a trace were independent; Section 17.1 measures N_{eff} near ten of 201, so the true F_N is flatter still and cutting N costs *less* than this says — conservative in direction, but not to be pushed past $N \approx N_{\text{eff}}$, where the collapse stops being resolved. And N is not a free dial: frame rate and window length set it, so a smaller N means a slower camera or a shorter record.

It folds into the certified problem, once the candidates are priced. This section previously stopped here, on the grounds that folding the split into the geometry optimization needs Σ at a geometry nobody has run. It folds in exactly. Let a candidate be a *pair* (x, N) — a geometry and a number of samples per trace — and let ξ allocate *trials* rather than runs. Then (53) gives

$$F = \sum_i J_i (\Sigma + F_{N_i}(x_i)^{-1})^{-1} = J \sum_i \xi_i M_i, \quad (54)$$

still linear in ξ , so log det is still concave and Equation (36) still applies. What breaks is the tacit assumption that candidates cost the same: an N -sample trace costs N frames. Normalizing by cost rather than by count, $\sum_i \xi_i c_i = 1$, ranges ξ over the set with vertices e_i/c_i , which is convex; the substitution $\eta_i = \xi_i c_i$ maps it onto the standard simplex with $M(\xi) = \sum_i \eta_i (M_i/c_i)$. So the search is the one **optimal measure** already certifies, run on the matrices divided by their prices, and the certificate returns in its cost-normalized form,

$$\xi^* \text{ is optimal} \iff \text{tr}[M(\xi^*)^{-1}M(x)]/c_x \leq p \text{ for all } x, \quad (55)$$

with equality on the support: a candidate earns runs when its information *per unit price* clears the bar. `pyimr.measure.budgeted.measure` is this, and it composes with the cardinality floor of (46) because both are substitutions in the same η .

Measured under (54) and certified by (55), on the 15 °C record at its own 3618 frames, against the geometry-only formulation with N pinned at 201:

one bubble costs	joint (nats)	geometry only	gained	N funded
0 frames	27.70	17.72	+9.99	6
25 frames	22.78	17.37	+5.41	6
100 frames	19.18	16.51	+2.67	12
400 frames	15.33	14.43	+0.90	25

all certified below 10^{-9} . The price of one bubble against one frame is not knowable from here, so it is swept; the gain exceeds the 1.34 nats Section 15 attributes to choosing the geometry at every price below about 400 frames a bubble. Holding the batch to five settings, so (16) keeps a numerator, costs 0.008 to 0.034.

Σ is the assumption, and it is both weaker and less load-bearing than the paragraph above assumed — though it inherits the standing caveat of Section 11 like everything else here. Weaker, because Σ is a population covariance of *material* parameters — a property of the gel and of how repeatably the laser nucleates, not of how large the bubble is — and the three records measuring it differ in *temperature*, not geometry, sitting at 277, 298 and 312 μm . There is no evidence of geometry dependence because geometry was never varied. Less load-bearing, because swept over $\times \frac{1}{2}$ to $\times 2$ the recommended N moves once, from 12 to 8.

What does bind is validity. At the two cheapest bubble prices N pins at the bottom of the grid, and that is a limit of the model rather than an optimum: F_N is scaled linearly in N here while N_{eff} is near ten of 201, so below that the linear form claims resolution the record does not have.

Nor do they survive the noise model

Every Fisher matrix, expected gain and batch in this chapter is built on a single number: $\sigma = 0.018 R_{\text{max}}$ at every sample. Fitting has never used it — the likelihood of Section 3.2 takes the per-sample spread — so this is a gap between the two halves of this document rather than an error inside either. The records disagree with the constant by two to three orders of magnitude *within one trace*: 124 $\times$, 882 $\times$ and 1316 $\times$ between the smallest and largest σ_i , around medians of 0.018 to 0.023.

At the same Jacobian, the constant overstates log det F by 1.3 to 2.2 nats and understates each parameter's standard deviation by up to a factor of two. What matters more is that it changes the answer. Transferring

each record’s measured profile to a candidate geometry by phase — reading σ as a function of t/t_c , which Section 5.3 justifies by showing the profile is dynamical rather than instrumental — the single best geometry moves from 514 μm at stretch 6.9 to 416 μm at 10.9, and the constant’s choice gives up as much as 1.34 nats of 8.89, fifteen percent.

The transfer is the assumption here, so it was tested rather than asserted. Under a raw per-sample profile the records split, 15°C keeping the constant’s geometry. Median- filtering the spread before transferring — a standard deviation from seven to eighteen trials carries 17 to 29% relative error and should not be interpolated raw — makes all three records agree on 416 μm at 10.9, and none agrees with the constant. The disagreement that survives is with the flat scale, not among the records, which is the opposite of what a transfer artifact looks like. Transferring by absolute time instead picks a different geometry again and is wrong for a statable reason: t_c spans a factor of twenty-four across the candidates, so the same clock time lands at a different point of the collapse.

Testability is what it really costs. The portfolio of Section 12 spends twelve runs over six geometries and carries $\text{df} = +2$. Under two of the three measured profiles it spreads over *four* and $\text{df} = 0$: the lack-of-fit test has no power at all. So (45) is not a formality the portfolio satisfies unaided, and the floor has to be imposed. Holding the measure to five settings with `constrained_measure` restores $\text{df} = +1$ for 0.010 and 0.084 nats of 36.5 — two tenths of one percent — and every constrained measure is certified under its floor.

One batch, chosen against the hardest case. Three profiles give three batches, and a recommendation has to be one. Averaging the gain across profiles is the move Section 12 already makes across questions, and it fails here: the weighted batch has the *worst* worst case of the five compared, 0.211 nats behind, below the flat-scale batch it was meant to improve on. Maximizing an average does not maximize a minimum. What works needs no machinery — one profile binds for every batch, so the worst case is always that column and the maximin answer is the argmax under it. When one member of a family is uniformly hardest, robust design is design against the hardest member.

The batches differ by 0.211 nats of 33.4, six tenths of a percent, so information barely separates them; settings run from five to eight and df from +1 to +4, so testability does. The batch recommended here wins on both:

R_{max} (μm)	stretch	runs
50	20.0	1
272	17.4	1
416	10.9	2
514	5.6	2
514	6.9	1
636	5.6	1
786	6.9	1
1200	6.9	3

eight settings, $\text{df} = +4$. Read it with Section 15: how the twelve runs are split between bubbles and frames is worth more than which geometries they visit.

The recommended geometries do not survive model error

Optimal designs are computed assuming the model is right. Ours is not: (16) says so at every temperature. The literature on sloppy systems warns that a model can fit worse on data from its own optimal experiment, and that is testable before a bubble is spent.

The test must not generate data from the model being fitted — that is the assumption under examination, and a study that makes it finds nothing. So the truth carries physics the fitted model lacks, and cold one-mode qSLS is fitted to it at four geometries. Two mismatches are used, because one would not distinguish a property of the design from a property of the missing physics: thermal transport, which Section 7 sizes at 16 noise units, and a second relaxation mode, at 14.4.

geometry	thermal truth			two-mode truth		
	χ^2/N	$g\alpha$ err	model err	χ^2/N	$g\alpha$ err	model err
performed, 277 μm at 7.09	1.231	3.8%	0.53	0.905	5.0%	0.11
E-optimal, 199 μm at 3.55	2.533	5.9%	1.24	0.877	4.9%	0.19
discrimination-optimal, 100 μm at 20.0	2.197	37.1%	1.17	1.915	60.7%	1.06
measure support, 60 μm at 18.0	0.892	5.2%	0.15	0.909	43.5%	0.25

One result holds under both mismatches, and it is the strongest thing here. The **discrimination-optimal geometry is worse on both counts, both times**: it fits 1.8 and 2.1 times worse than the geometry already performed, and recovers $g\alpha$ 9.8 and 12.2 times worse. A design chosen to separate constitutive models degrades the parameter it was supposed to help measure, whichever physics is missing.

The rest does not survive the change of mismatch, and saying so is the point of running two. Under thermal error the E-optimal geometry loses on both counts; under constitutive error it is indistinguishable from the performed one (0.97 and 0.98). The 60 μm support point reverses more sharply: it carries the least model error under thermal truth and recovers $g\alpha$ 8.7 times worse under two-mode truth.

So the sloppy-systems warning is not simply confirmed. What these records support is narrower and, for a collaborator, worse: *which design is safe depends on which physics is missing, and we do not know which is missing*. Equation (16) says the model is inadequate on every record; it does not say in what direction. A design cannot be certified robust without naming the model error it is robust to, and no criterion in Section 11 takes model error as an argument. Its *magnitude* is available even though its direction is not: Equation (21) bounds what the unseen half can do to the parameters a design is optimising, which is the difference between an unquantified worry and a term one could eventually carry. Section 15 carries it, by making the measured $\hat{\delta}$ a coordinate rather than a bound — which is as far as one direction gets you, and is why the qualification in that subsection is about calibration rather than about existence.

The mechanism is visible in the model-error columns. A criterion computed under the correct-model assumption sends the experiment where the model is most *sensitive*, which is often where it is most *wrong*: the thermal mismatch grows from 0.53 noise units at the performed geometry to 1.24 at the E-optimal one, and the fitted parameters absorb it. That mechanism is general. Which geometry it punishes is not.

Making the discrepancy a coordinate

“No criterion in Section 11 takes model error as an argument” is the sentence above, and it need not stand. Section 12 treats model inadequacy as unreachable because it is not a *coordinate* — no column of the Jacobian points at it — which is why testability enters as the cardinality constraint (45) rather than as anything optimized for. But Section 10 does not merely bound $\hat{\delta}$; it extracts it as a vector.

Write $m(\theta) + \eta \hat{\delta}$ and treat η exactly as Section 13 treats the model label: one more column of J . Its variance after the material is fitted out,

$$\text{Var}(\eta) = \left(\|d\|^2 - d^T P d \right)^{-1}, \quad P = J(J^T J)^{-1} J^T, \quad (56)$$

is the part of the discrepancy a design can *see* rather than absorb. The two uses point the same way, which is what makes it worth having: testing the model wants $\hat{\delta}$ visible, and keeping the parameters clean wants it unabsorbed, and both are the same angle.

Carrying it to an unrun geometry needs the transfer of Section 15, under the standing caveat of Section 11, and the premise is checkable rather than assumed. Resampled onto a common t/t_c grid, the three records’ $\hat{\delta}$ overlap at 0.44, 0.42 and 0.81 against 0.05 for unrelated curves of that length — the same test, and the same verdict, that justified transferring σ by phase.

Scoring (56) at the four geometries Section 15 put through two synthetic mismatches:

geometry	$R_{\max}$	stretch	visible share	$g\alpha$ err (thermal)	(two-mode)
performed	277 μm	7.09	0.998	3.8%	5.0%
E-optimal	199 μm	3.55	0.972	5.9%	4.9%
discrimination-optimal	100 μm	20.0	0.876	37.1%	60.7%
measure support	60 μm	18.0	0.763	5.2%	43.5%

A single measured $\hat{\delta}$ cannot know which mismatch is the real one, so the most it can predict is what the two have in common. It does: the rank correlation of visible share against the parameter error is -0.40 under thermal truth and -0.60 under two-mode truth, both of the predicted sign, from four points. That is weak evidence and it is the right amount to claim — what it establishes is that the criterion is not refuted, not that it is calibrated.

The criterion also disagrees with the one the chapter has been using, which is the reason to carry it: material log det is largest at $89\text{ }\mu\text{m}$ and stretch 20, where 83.7% of $\hat{\delta}$ is visible, while visibility is largest at $1200\text{ }\mu\text{m}$ and stretch 20 at 99.0%. The worst geometry on the grid hides two fifths of it.

16 Temperature dependence

The most informative result is not any single number but a trend (Figure 22). The advantage that the stiffening term buys over pure relaxation shrinks monotonically as the gel warms: the gap between SLS and qSLS falls from 2.94 versus 1.35 at $15\text{ }^{\circ}\text{C}$ to 1.41 versus 1.23 at $33\text{ }^{\circ}\text{C}$. A warmer, softer gel needs less strain-stiffening to explain its record. Because this is a trend across three independent datasets rather than a single fitted value, it is harder to attribute to a fitting artifact than any individual χ^2 .




Figure 22: What the stiffening term buys, against temperature. The advantage of qSLS over SLS narrows as the gel warms.

17 Conclusions

We have treated the model comparison in inertial microcavitation rheometry as the object of study rather than a step toward a parameter value. Ranking by evidence in coordinates the records can answer, three findings hold.

The shear modulus is not identified separately from the stiffening exponent, so a reported modulus is a statement about the prior box – and Section 10 shows this is not a bound that can be widened away, since releasing one wall merely slides the fit onto another. The bubble-dynamics operator assumed throughout this literature is beaten on every record. And a correlated residual that has been read as constitutive model error survives every constitutive, observational and operator change tested here.

Two of those findings needed qualifying once the equilibrium radius was fitted rather than asserted. Compressibility is required on every record at every prior width, by 74 to 179 nats. Gilmore still beats the pressure form at $15\text{ }^{\circ}\text{C}$. But at $23\text{ }^{\circ}\text{C}$ and $33\text{ }^{\circ}\text{C}$ the operator margins collapse to under a nat, so those records never discriminated operators at all – pinning R_{eq} is what made it appear they did. The fit wants R_{eq} 3% to 11% larger than inferred, consistently across six operators and three records, and we cannot yet explain the trend with temperature.

On the design side the useful conclusion is about what to optimize rather than what the optimum is. The certified formulation was applied to the geometry, which its own numbers rank last: pricing the candidates so

the bubbles-against-frames split enters the same convex problem buys 0.9 to 10 nats against at most 1.3 for the geometry, and the certificate survives the change intact because normalizing by cost is the same simplex in different coordinates. Three further questions the chapter raised are now answered, and two of the answers are negative. The screening cliff Section 14 calls a precondition is removed by a maximin over the deflation, at no worst-case cost. Staging a budget is worth nothing, because one bubble at a geometry chosen for the operator question settles every live rival — which says the operator margins reported here are small for want of a geometry, not for want of runs. And the temperature dependence cannot be identified at all without varying temperature, which no design in this literature does.

What remains genuinely open is the one thing a criterion still cannot take as an argument: which physics is missing. Section 15 gets as far as the measured δ allows, and the transfer it rests on is supported rather than established.

17.1 Limitations of this work

The 33 °C correlated fits are not usable. Recomputing the operator evidences with Σ in the likelihood behaves on two records and not on the third. At 15 and 23 °C the compressible operators collapse to within a third of a nat of each other and Rayleigh–Plesset lands a few nats below, which is a sensible picture of data that cannot order six similar equations. At 33 °C the same computation puts Rayleigh–Plesset at -1.1×10^4 to -2.8×10^4 and separates two compressible operators by 200 to 550 nats.

Three orders of magnitude out of family with the other two records is not a physical result. The mechanism is visible in the construction: whitening by an exponential covariance amplifies whatever fine structure a residual has by about $1/(1 - \rho^2)$, and a residual with a little high-frequency content left in it therefore produces an enormous χ^2 that says more about the conditioning of Σ than about the model. The record with the fewest trials — seven against eighteen — has the noisiest spread and so the least reliable whitening. These numbers are reported here so they are not mistaken for evidence, and excluded from every conclusion.

The dropped points are outside the model, not outside the solver. Roughly one point in six of the winner’s parameter box cannot be integrated, and that is not a numerical shortcoming. In that region the model expands to $R/R_0 = 2132$ after its collapse – identically at relative tolerances of 10^{-3} , 10^{-4} and 10^{-5} . So it is a converged property of the equations, not an artifact. The bubble begins at its maximum radius and its energy is finite, so growth of that size is the constitutive model failing. Refusing those points is the correct outcome.

The count of admissible points is pinned near 1958 of 2401 sampled whatever the settings. Looser tolerances and a $20\times$ step budget convert failures into runaways, never into usable solves. This corrects an earlier reading of the same failures as a stiffness problem. The dropped points cannot be recovered by numerical effort, and no claim about the winner’s fit should be made in that region.

The ranking survives; the parameter estimates do not. Independent sequential Monte Carlo runs give the winner 2173.55 ± 0.19 in log evidence against 2071.90 ± 0.38 for the relaxation-only model – a gap of 101.6 against run-to-run noise near 0.4, so the comparison is resolved by a wide margin. The tensor grid cannot say this on its own: it returns a single number with no uncertainty.

The same grid cannot estimate parameters. Refining it from 12 to 20 points per axis moves the log evidence by 17.3, and moves the best-fit point from $g = 658$, $\alpha = 1.52$ to $g = 144$, $\alpha = 8.86$. The best cell is simply whichever node lands nearest the ridge.

Refinement cannot fix this. The posterior standard deviations are 0.0018, 0.0025, 0.0055 and 0.078 in unit coordinates, against a grid spacing of 0.053. The posterior therefore occupies about 10^{-7} of the prior volume, and a uniform grid would need of order 10^{10} points. Discretization error of 17.3 sits well inside the 101.6 gap, so the ranking is safe; the reported best-fit parameters are not. Figure 24 shows which models lose points.

Consequences for the numbers reported here. Three methods that resolve the posterior – sampling, a refined grid, and continuous optimization – agree that g lies near 10^2 Pa. The coarse grid used for the ranking reports 2154 Pa. The ranking does not depend on this; any material property quoted from the grid does.

A modulus that size is also implausibly soft for gelatin. That is the degeneracy above making itself felt: the fit buys a lower residual by trading modulus against stiffening, along a direction the data barely constrain.




Figure 23: Where the winner can be integrated, at the fitted modulus and viscosity. Failure is governed principally by the stiffening, and the threshold falls to its lowest where the relaxation time is comparable to the bubble's own period – but it is a boundary that moves, not an isolated band.




Figure 24: Fraction of each model's parameter grid that could not be integrated. Models not shown lost no points.

One candidate was never genuinely exercised. The Gent solid appears in the comparison but cannot be tested on these records. Its energy diverges as $I_1 - 3 \rightarrow J_m$, and a Gent solid soft enough to be distinguishable from Neo-Hookean predicts a collapse it cannot sustain, so it locks up. Where it does integrate, it differs from Neo-Hookean by 1.7×10^{-4} of $R_{\max}$ against measurement noise near 2×10^{-2} – two orders of magnitude below what the data can resolve. Any statement about strain-stiffening laws here excludes it.

A Statistical background

This appendix develops, from first principles, the results the main text uses. It is self-contained and assumes only calculus and elementary probability.

A.1 Inference as conditioning

Write θ for parameters, y for data, M for a model. The product rule $p(\theta, y) = p(y | \theta) p(\theta) = p(\theta | y) p(y)$ rearranges to Bayes' theorem,

$$p(\theta | y, M) = \frac{p(y | \theta, M) \pi(\theta | M)}{p(y | M)}, \quad p(y | M) = \int p(y | \theta, M) \pi(\theta | M) d\theta. \quad (57)$$

The denominator is a normalizing constant in θ , which is why it is ignored when estimating parameters and why it is the entire content of model comparison: applying (57) at the level of models gives

$$\frac{p(M_1 | y)}{p(M_2 | y)} = \underbrace{\frac{p(y | M_1)}{p(y | M_2)}}_{\text{Bayes factor } B_{12}} \cdot \frac{p(M_1)}{p(M_2)}. \quad (58)$$

Everything the data say about which model to prefer is in B_{12} . Jeffreys' conventional reading takes $\log B > 1$ as substantial and $\log B > 5$ as decisive; the gap reported here is over 100, which is why its numerical resolution had to be checked rather than assumed.

A.2 The score, and two definitions of information

Let $\ell(\theta) = \log p(y | \theta)$. The *score* is $u = \nabla_\theta \ell$. Since $\int p(y | \theta) dy = 1$ for every θ , differentiating under the integral gives

$$\mathbb{E}_\theta[u] = \int \frac{\nabla p}{p} p dy = \nabla \int p dy = 0, \quad (59)$$

so the score has zero mean at the true parameter. Its covariance defines the Fisher information, $F = \mathbb{E}[uu^\top]$. Differentiating the same identity twice gives the equivalent and more useful form

$$F = \mathbb{E}[-\nabla^2 \ell], \quad (60)$$

the expected curvature. The two agree because $\nabla^2 \log p = \nabla^2 p/p - (\nabla p/p)(\nabla p/p)^\top$ and the first term integrates to zero. Curvature and variance-of-score are the same object, which is the reason a sharply peaked likelihood and a precisely determined parameter are the same statement.

A.3 The Cramér–Rao bound

For an unbiased estimator $\hat{\theta}(y)$, differentiate $\mathbb{E}[\hat{\theta}] = \theta$ under the integral to get $\mathbb{E}[\hat{\theta} u^\top] = I$. Applying the Cauchy–Schwarz inequality to the pair $(\hat{\theta} - \theta, u)$ in the scalar case gives $\text{Var}(\hat{\theta}) \mathbb{E}[u^2] \geq 1$, i.e. $\text{Var}(\hat{\theta}) \geq 1/F$; the multivariate statement is

$$\text{Cov}(\hat{\theta}) \succeq F^{-1}. \quad (61)$$

So F^{-1} is a floor on achievable precision, attained asymptotically by maximum likelihood: $\sqrt{N}(\hat{\theta}_N - \theta) \rightarrow \mathcal{N}(0, F_1^{-1})$ under regularity. This is the license for reading F^{-1} as a covariance and its eigenvectors as the axes of a confidence ellipsoid – and the regularity conditions are exactly what near-singular F threatens, which is why sloppiness is worth detecting rather than tolerating.

A.4 Gaussian data, and why $F = J^\top J$

With independent Gaussian observations of known deviation, $\ell = -\frac{1}{2} \sum_i (y_i - m_i(\theta))^2 / \sigma_i^2 + \text{const}$. Then

$$\frac{\partial \ell}{\partial \theta_j} = \sum_i \frac{y_i - m_i}{\sigma_i^2} \frac{\partial m_i}{\partial \theta_j}, \quad -\frac{\partial^2 \ell}{\partial \theta_j \partial \theta_k} = \sum_i \frac{1}{\sigma_i^2} \left[\frac{\partial m_i}{\partial \theta_j} \frac{\partial m_i}{\partial \theta_k} - (y_i - m_i) \frac{\partial^2 m_i}{\partial \theta_j \partial \theta_k} \right]. \quad (62)$$

Taking the expectation kills the second bracket because $\mathbb{E}[y_i - m_i] = 0$, leaving $F = J^\top J$ with $J_{ij} = \sigma_i^{-1} \partial m_i / \partial \theta_j$. Note what was discarded: the curvature of the model. At the optimum the residuals are small and the Gauss–Newton form is accurate; far from it, or with a badly misspecified model, F and the observed Hessian differ, and the discrepancy is itself a diagnostic.

A.5 The Laplace approximation and the Occam factor

To evaluate $Z = \int e^{\ell(\theta)} \pi(\theta) d\theta$, expand about the maximum $\hat{\theta}$ where $\nabla \ell = 0$:

$$\ell(\hat{\theta} + \delta) = \ell(\hat{\theta}) - \frac{1}{2} \delta^\top H \delta + O(\|\delta\|^3), \quad H = -\nabla^2 \ell(\hat{\theta}). \quad (63)$$

Holding π constant over the peak and using $\int e^{-\delta^\top H \delta / 2} d\delta = (2\pi)^{p/2} |H|^{-1/2}$,

$$Z \simeq e^{\ell(\hat{\theta})} \pi(\hat{\theta}) (2\pi)^{p/2} |H|^{-1/2}. \quad (64)$$

The correction is $O(N^{-1})$ relative for regular problems. Writing the posterior volume as $V_{\text{post}} = (2\pi)^{p/2} |H|^{-1/2}$ and the prior density as $1/V_{\text{prior}}$ where it is flat, the second factor is $V_{\text{post}}/V_{\text{prior}}$: the fraction of the space the data leave standing. A model with more parameters has a larger V_{prior} and pays for it unless the fit improves enough to compensate. Nothing was added by hand; the penalty is the Jacobian of the integral.

Taking logarithms of (64), using $H \approx NF_1$ for N independent observations, and dropping terms that do not grow with N ,

$$-2 \log Z \simeq -2\ell(\hat{\theta}) + p \log N + O(1), \quad (65)$$

which is the Bayesian information criterion. BIC is therefore not an alternative to the evidence but a coarse asymptotic of it, valid when the posterior is Gaussian, the parameters identified, and N large. AIC answers a different question – expected out-of-sample Kullback–Leibler divergence – and is not an approximation to Z at all. Where a model is sloppy, H is near-singular, $|H|^{-1/2}$ is enormous, and the asymptotic form fails while the integral remains well defined.

A.6 What a nat means here

Three sections report a log evidence for the same model on the same record and they disagree by a factor of four: -2289.86 from the grid quadrature, $+529.26$ from the capped Laplace expansion of Section 5.4, and $+2173.55$ from the sequential Monte Carlo of Section 17.1. Every threshold in this document is stated in nats, so this has to be said rather than left to inference.

An evidence is defined only up to the normalisation of its likelihood, and the term that moves is $-\frac{1}{2} \sum_i \log(2\pi\sigma_i^2)$. Recomputed at one fit on the 15 °C record:

σ convention	χ^2/N	$-\chi^2/2$	$-\frac{1}{2} \sum \log 2\pi\sigma^2$	Occam	$\log Z$
trial spread	0.971	-97.6	+640.6	-15.9	527.1
standard error, $/\sqrt{18}$	17.478	-1756.6	+931.1	-20.3	-845.7

The two conventions differ by 1373 nats on one residual — 290 of it the $N \log \sqrt{J}$ shift and the rest the χ^2 , which scales by J rather than shifting. This is the same choice Section 5.3 shows moving χ^2/N from 0.974 to 17.54, and it moves $\log Z$ far more.

Against that decomposition the three reported numbers resolve as follows. The capped Laplace is reproduced to 2.15 nats, so Section 5.4 uses the trial spread and the expansion of (67). The grid quadrature is not this integral at all: Section 2 adds a marginalised noise scale, a redundancy weight and a BIC-style penalty, and




Figure 25: The Occam factor is the share of the prior the data leaves standing, $\prod_k \sqrt{2\pi/\lambda_k}$ over the eigenvalues of $J^T J$. Left: every direction is narrower than its prior, so a flexible model pays for volume it does not use. Right: a direction the data does not determine has $\lambda_k \rightarrow 0$, the fitted Gaussian extends far outside the box the prior occupies, and the expansion returns a factor *greater* than one – the evidence rises when a useless parameter is added. Capping each direction at unity, (67), restores what the geometry already required; on the models of Section 5.4 the uncapped form favored the two-mode law by 29.7 nats exactly where its second arm did nothing.

quadratures a box rather than expanding about a mode, which accounts for its being 2817 nats away. The sequential Monte Carlo sits 1646 above the Laplace on the same convention and is *not* reconciled here.

What saves the document’s conclusions is that every comparison it draws is made *within* one pipeline — SMC against SMC for the 101.6-nat constitutive gap, Laplace against Laplace for the enrichment margins. Those are valid. What is not valid, and what a reader should not attempt, is differencing a number from one section against a number from another. The five-nat threshold of (47) is meaningful only against margins computed the same way, and it is applied to Laplace-scale margins throughout.

A.7 Capping the Occam factor at the prior

The failure just noted is not merely a loss of accuracy; it has a sign, and the sign is wrong. Work in coordinates where the prior is uniform on the unit cube, so $V_{\text{prior}} = 1$ and $H = J^T J$. The Occam factor is a product over the eigendirections of $J^T J$,

$$\frac{V_{\text{post}}}{V_{\text{prior}}} = \prod_{i=1}^p \sqrt{\frac{2\pi}{\lambda_i}}, \quad (66)$$

each factor being the posterior width in that direction against a prior of width one. A direction the data does not determine has $\lambda_i \rightarrow 0$ and contributes a factor diverging to $+\infty$. The evidence then *increases* with the addition of a parameter that does nothing, which is the opposite of what the Occam factor exists to do.

The pathology is entirely an artifact of the Gaussian approximation. The fitted Gaussian has width $\sqrt{2\pi/\lambda_i} \gg 1$ in that direction and so extends far outside the cube the prior actually occupies, while the true integral, taken over the cube, simply returns the prior mass. Imposing what the geometry already requires – a posterior cannot be wider than the prior it came from – gives

$$\log \frac{V_{\text{post}}}{V_{\text{prior}}} = \sum_{i=1}^p \min\left(0, \frac{1}{2} \log \frac{2\pi}{\lambda_i}\right), \quad (67)$$

so a direction the data cannot see costs nothing and buys nothing. Where every $\lambda_i > 2\pi$ each minimum selects its second argument and (67) reduces identically to the logarithm of (66): the cap is a strict generalization, altering an answer only where the uncapped form was not entitled to one. Section 5.4 gives the size of the error it removes, which on the models considered there is 29.7 nats.

This matters wherever models of differing dimension are compared and some parameters are weakly identified – which, for the sloppy spectra of Section A.8, is the normal case rather than the exceptional one.




Figure 26: Why a “best fit” for g is a statement about the prior. The likelihood depends on the product $g\alpha$, so the misfit surface is a valley running along constant $g\alpha$ and the data is flat along g/α . An optimizer slides until it meets the edge of the box, and *where* it stops is set by the box: the two dashed rectangles give the two filled points, which differ in g by more than thirtyfold. This is the mechanism behind the fifty-nat swing in the operator ranking of Section 6 when the bounds were widened, and behind the order-of-magnitude disagreement in g between methods in Figure 9.

A.8 Sloppy models

Write the eigen-decomposition $F = V\Lambda V^T$ with $\lambda_1 \geq \dots \geq \lambda_p$. The misfit near the optimum is $\Delta\chi^2 = \sum_k \lambda_k c_k^2$ for $\delta = \sum_k c_k v_k$, so moving a distance c along v_k costs $\lambda_k c^2$ and the 95% contour lies at $c_k = \sqrt{3.84/\lambda_k}$. Multiparameter models of this kind generically show spectra spanning many decades, with a few stiff directions and many sloppy ones – the observation of Gutenkunst [19], Sethna and co-workers, and the reason parameter values in such models are often far less determined than their predictions.

The distinction to keep is between a rank-deficient F , where a direction is *structurally* unidentifiable and no experiment helps, and a merely ill-conditioned F , where the direction is determined but weakly. In logarithmic parameters, an eigenvector is a power-law combination, and the invariant it leaves fixed is read off its components.

A.9 Correlated errors

Let r be the residual vector with covariance C . The Gaussian log-likelihood is

$$-2\ell = r^T C^{-1} r + \log |C| + N \log 2\pi, \quad (68)$$

and with the Cholesky factorization $C = LL^T$ this becomes $\|L^{-1}r\|^2 + 2\sum_k \log L_{kk} + \text{const}$: whitening turns generalized least squares back into ordinary least squares on transformed residuals. Ignoring the off-diagonal terms, i.e. using $\text{diag}(C)$, does not merely lose efficiency – it misstates the amount of information. For a stationary sequence with autocorrelation ρ_k ,

$$\text{Var}\left(\sum_{i=1}^N r_i\right) = N\sigma^2 \left(1 + 2\sum_{k=1}^{N-1} \left(1 - \frac{k}{N}\right)\rho_k\right) \xrightarrow{N \rightarrow \infty} N\sigma^2 \left(1 + 2\sum_{k \geq 1} \rho_k\right), \quad (69)$$

so the sequence carries the information of $N_{\text{eff}} = N/(1 + 2\sum \rho_k)$ independent draws. The bracket is the spectral density of the residual sequence at zero frequency, which is the cleaner way to see why a long-range correlation is so costly.

Correlated residuals in a *fitted* model usually indicate model discrepancy rather than correlated measurement noise. Kennedy and O’Hagan [10] formalize this by writing $y = m(\theta) + \delta(\cdot) + \varepsilon$ with δ a Gaussian process, and Brynjarsdóttir and O’Hagan show that omitting δ leaves parameter estimates biased *and* overconfident, while an unconstrained δ absorbs the physics. Neither failure is visible in χ^2 .




Figure 27: Two failures that look alike in a fit and differ completely in what can be done about them. Left: the misfit is exactly flat along a direction, F is singular, and the parameter combination is structurally unidentifiable. No experiment recovers it, and only a reparameterization or a fixed value helps. Right: the misfit is closed but very elongated, F is invertible and ill-conditioned, and the combination is determined weakly. Here a design that rotates the ellipse can close it, which is what Section 11 sets out to do. On these records $\lambda_{\min} = 5.2 \times 10^{-2} \neq 0$, so the problem is the second kind.




Figure 28: Why some parameter combinations are determined and others are not. Near the best fit the misfit rises as a quadratic form, so the contour of constant misfit is an ellipse whose axes point along the eigenvectors of $F = J^T J$ and whose half-lengths go as $1/\sqrt{\lambda}$. A large eigenvalue is a short axis: move that way and the fit degrades at once. A small one is a long axis: move that way and the data barely object. On these records the ratio is 1.1×10^3 , and the long direction is g up with α down at fixed product, which is the ridge of Figure 26 seen from above. The ellipse is drawn at an aspect of about 8 : 1; the measured aspect is $\sqrt{1.1 \times 10^3} \approx 33 : 1$, which would render as a line.

A.10 Optimal experimental design

A design ξ determines what is measured and hence $F(\xi, \theta)$. Since F is a matrix and designs must be ranked, a scalar functional is required, and the classical choices are

$$\Phi_D = \log \det F, \quad \Phi_A = -\text{tr } F^{-1}, \quad \Phi_E = \lambda_{\min}(F), \quad \Phi_c = -c^T F^{-1} c, \quad (70)$$

each maximized. In Bayesian terms, Φ_D is the expected Kullback–Leibler gain from prior to posterior under a Gaussian approximation, which is why it is the default: it maximizes information about *all* parameters jointly. That default is wrong whenever one direction is the question, because $\log \det F = \sum_k \log \lambda_k$ is dominated by the large eigenvalues.

Because F depends on θ , a local design presupposes an answer. The standard repairs are to average over a prior, $\Phi(\xi) = \mathbb{E}_\theta[\Phi(F(\xi, \theta))]$, or to take the worst case over a plausible set. Sequential design uses the posterior from completed experiments as the prior for the next, which is what is done here.

When the model itself is uncertain, all of the above presuppose the wrong thing. T-optimality (Atkinson and Fedorov) maximizes instead the lack of fit of the inferior model,

$$\Phi_T(\xi) = \min_{\theta_2} \|m_1(\hat{\theta}_1; \xi) - m_2(\theta_2; \xi)\|^2, \quad (71)$$




Figure 29: Why 201 samples do not carry 201 samples’ worth of evidence. The residuals here are strongly correlated from one sample to the next, so neighboring points repeat information rather than adding it. A correlated sequence carries what $N_{\text{eff}} = N/(1 + 2 \sum_k \rho_k)$ independent draws would, and on these fits N_{eff} is near 8. Both χ^2/N and the evidence assume the samples are independent, so each overstates the information by roughly $N/N_{\text{eff}} \approx 25$. A margin of a few nats between two models is inside that factor.

which asks which experiment the candidates most disagree about. Its virtue here is that it shares no assumptions with the Fisher criteria, so agreement between them is evidence rather than restatement.

B Reproducing

```
.venv/bin/python examples/measured_selection.py <dataset> [thermal Nt] [workers]
.venv/bin/python docs/writeup/collect.py 16      # records results.json
.venv/bin/python docs/writeup/figures.py         # draws every figure from it
```

Every number and figure in this document comes from `results.json`; none is transcribed by hand.

Code and data availability

Every number and figure in this document is reproduced by scripts in the repository that contains it: `figures.py`, `figures_geometry.py`, `figures_identifiability.py`, `figures_measure.py` and `figures_trial.py` draw the figures, `fit_quality.py` the fit table and `trial_variation.py` the trial-spread analysis, each from the tracked `results.json`. The design measures use `pyimr.measure`, the discrimination criteria `pyimr.discriminate`, and the trade-off front `pyimr.pareto`.

The design results added in Sections 13 to 15 come from `allocation_measure.py` (the priced joint measure), `discrepancy_design.py` ($\hat{\delta}$ as a coordinate), `correlated_design.py` (the correlated likelihood), `screen_maximin.py` (the deflation maximin), `two_stage.py` (staging) and `temperature_design.py` (the Arrhenius axis). The measured records themselves are not redistributed here.

References

- [1] Jonathan B. Estrada, Carlos Barajas, David L. Henann, Eric Johnsen, and Christian Franck. High strain-rate soft material characterization via inertial cavitation. *Journal of the Mechanics and Physics of Solids*, 112:291–317, 2018.
- [2] Jonathan B. Freund and Randy H. Ewoldt. Quantitative rheological model selection: Good fits versus credible models using Bayesian inference. *Journal of Rheology*, 59(3):667–701, 2015.
- [3] J. Kiefer and J. Wolfowitz. The equivalence of two extremum problems. *Canadian Journal of Mathematics*, 12:363–366, 1960.
- [4] Joseph B. Keller and Michael Miksis. Bubble oscillations of large amplitude. *The Journal of the Acoustical Society of America*, 68(2):628–633, 1980.
- [5] Charles J. Geyer. Practical Markov chain Monte Carlo. *Statistical Science*, 7(4):473–483, 1992.

- [6] Andrea Prosperetti and Adriano Lezzi. Bubble dynamics in a compressible liquid. Part 1. First-order theory. *Journal of Fluid Mechanics*, 168:457–478, 1986. doi: 10.1017/S0022112086000460.
- [7] Olivier Le Métayer and Richard Saurel. The Noble–Abel stiffened-gas equation of state. *Physics of Fluids*, 28(4):046102, 2016. doi: 10.1063/1.4945981.
- [8] Adriano Lezzi and Andrea Prosperetti. Bubble dynamics in a compressible liquid. Part 2. Second-order theory. *Journal of Fluid Mechanics*, 185:289–321, 1987. doi: 10.1017/S0022112087003185.
- [9] Bachir A Abeid, Mario L Fabiilli, Mitra Aliabouzar, and Jonathan B Estrada. Experimental & numerical investigations of ultra-high-speed dynamics of optically induced droplet cavitation in soft materials. *J. Mech. Behav. Biomed. Mater.*, 160:106776, 2024.
- [10] Marc C. Kennedy and Anthony O’Hagan. Bayesian calibration of computer models. *Journal of the Royal Statistical Society: Series B*, 63(3):425–464, 2001.
- [11] Milton S. Plesset. On the stability of fluid flows with spherical symmetry. *Journal of Applied Physics*, 25(1):96–98, 1954.
- [12] A. C. Atkinson and V. V. Fedorov. The design of experiments for discriminating between two rival models. *Biometrika*, 62(1):57–70, 1975.
- [13] D. V. Lindley. A statistical paradox. *Biometrika*, 44(1–2):187–192, 1957.
- [14] Harold Jeffreys. Some tests of significance, treated by the theory of probability. *Mathematical Proceedings of the Cambridge Philosophical Society*, 31(2):203–222, 1935.
- [15] S. D. Silvey, D. M. Titterton, and B. Torsney. An algorithm for optimal designs on a finite design space. *Communications in Statistics — Theory and Methods*, A7:1379–1389, 1978.
- [16] A. C. Atkinson. DT-optimum designs for model discrimination and parameter estimation. *Journal of Statistical Planning and Inference*, 138(1):56–64, 2008.
- [17] R. D. Cook and W. K. Wong. On the equivalence of constrained and compound optimal designs. *Journal of the American Statistical Association*, 89(426):687–692, 1994.
- [18] Friedrich Pukelsheim and Sabine Rieder. Efficient rounding of approximate designs. *Biometrika*, 79(4):763–770, 1992. doi: 10.1093/biomet/79.4.763.
- [19] Ryan N. Gutenkunst, Joshua J. Waterfall, Fergal P. Casey, Kevin S. Brown, Christopher R. Myers, and James P. Sethna. Universally sloppy parameter sensitivities in systems biology models. *PLoS Computational Biology*, 3(10):e189, 2007.